

# REGIONAL HETEROGENEITY AND THE REFINANCING CHANNEL OF MONETARY POLICY\*

MARTIN BERAJA  
ANDREAS FUSTER  
ERIK HURST  
JOSEPH VAVRA

We argue that the time-varying regional distribution of housing equity influences the aggregate consequences of monetary policy through its effects on mortgage refinancing. Using detailed loan-level data, we show that regional differences in housing equity affect refinancing and spending responses to interest rate cuts, but these effects vary over time with changes in the regional distribution of house price growth. We build a heterogeneous household model of refinancing with mortgage borrowers and lenders and use it to explore the monetary policy implications arising from our regional evidence. We find that the 2008 equity distribution made spending in depressed regions less responsive to interest rate cuts, thus dampening aggregate stimulus and increasing regional consumption inequality, whereas the opposite occurred in some earlier recessions. Taken together, our results strongly suggest that monetary policy makers should track the regional distribution of equity over time. *JEL* Codes: E21, E52, G21.

## I. INTRODUCTION

Collateralized borrowing in the housing market can potentially play an important role in the monetary transmission mechanism, as interest rate cuts encourage households to refinance their

\*We thank Caitlin Gorbach, Karen Shen, and Eilidh Geddes for excellent research assistance. We also thank the editor (Robert Barro); four anonymous referees; our discussants, John Campbell, Wouter Den Haan, Daniel Greenwald, Amit Seru, Junyi Zhu, and Mark Zandi; as well as Adrien Auclert, Arlene Wong, and seminar participants at Chicago Booth, University of Minnesota, NYU, MIT Sloan, Berkeley Haas, IIES Stockholm, University of Zurich, Central Bank of Ireland, NBER Summer Institute, ECB Annual Research Conference, ASSA Chicago, SED-Edinburgh, SITE Stanford, Hutchins Center at Brookings, the Frontiers in Central Banking conference at the Bundesbank, Wharton, the Bank of Canada, and the CEPR–University of St. Gallen workshop on Household Finance and Economic Stability for helpful comments. Fuster was an employee of the Federal Reserve Bank of New York while this article was written. The views expressed in this article are solely those of the authors and not necessarily those of the Federal Reserve Bank of New York, the Federal Reserve System, or the Swiss National Bank.

© The Author(s) 2018. Published by Oxford University Press on behalf of the President and Fellows of Harvard College. All rights reserved. For Permissions, please email: [journals.permissions@oup.com](mailto:journals.permissions@oup.com)

*The Quarterly Journal of Economics* (2019), 109–183. doi:10.1093/qje/qjy021.  
Advance Access publication on September 3, 2018.

mortgage and extract home equity to fund current consumption.<sup>1</sup> Since housing markets are locally segmented, regional house price shocks are a critical determinant of home equity and the strength of this refinancing channel of monetary policy.

In this article, we argue that the time-varying regional distribution of home equity plays a crucial role in determining both the aggregate effects of monetary stimulus and whether this stimulus flows to the regions that need it most. Our analysis is motivated by striking differences across recessions in the cross-regional distribution of house price growth. During the Great Recession, house prices fell substantially on average, but declines varied greatly across space and were largest where economic activity also fell most (e.g., Nevada). In contrast, house prices grew on average throughout the 2001 recession with little regional variation. The resulting differences in the regional equity distribution across these recessions affect the refinancing channel of monetary policy for two reasons. First, lenders generally require a minimum level of equity to allow borrowers to refinance, even if they are not extracting equity. Second, the level of equity potentially extracted during refinancing clearly depends on the existing level of equity in the house prior to refinancing.

The article begins by using detailed micro-data to show that interest rate declines during the Great Recession mostly stimulated regions with the smallest declines in house prices (which also had the smallest increases in unemployment).<sup>2</sup> In contrast, refinancing was strongest in high unemployment regions in the 2001 recession, when regional house price growth was mostly uncorrelated with unemployment. Then we build a heterogeneous household model of refinancing and use it to explore aggregate implications of this regional evidence for monetary policy. Our model implies that interest rate cuts in 2008 indeed had the smallest effects on depressed regions. More important, the regional distribution of housing equity in 2008 substantially dampened the aggregate effects of monetary policy. Since the distribution of equity both varies across time and changes the consequences of monetary

1. See, for example, <https://www.federalreserve.gov/boarddocs/hh/2004/february/testimony.htm> and <https://www.newyorkfed.org/newsevents/speeches/2012/dud120106.html> for recent policy discussion of this channel.

2. Our empirical patterns in the QE1 episode are similar to those documented by [Caplin, Freeman, and Tracy \(1997\)](#) for the 1990 recession based on mortgage data from a single bank.

policy, we conclude that it is important for policy makers to track this variation. Furthermore, we show how certain mortgage market policy interventions can successfully complement monetary policy if the refinancing channel is again hindered in the future.

In more detail, the first half of our article provides empirical evidence that regional variation in housing equity matters for the refinancing channel of monetary policy. We start by studying the response of different regions to the large interest rate declines immediately following the first round of the Federal Reserve's large-scale asset purchase program—commonly called quantitative easing (QE1). Based on loan-level data, we document three facts about the regional response to QE1. First, there was a boom in household mortgage refinancing right after the QE1 announcement. Second, refinancing activity and the amount of equity extracted increased more in metropolitan statistical areas (MSAs) that had lower unemployment and where homeowners had more housing equity on the eve of QE1. Specifically, very little refinancing occurred in places like Las Vegas, where most homeowners were underwater when QE1 was implemented. Third, MSAs with the most refinancing right after QE1 also experienced the largest resulting increases in consumption, as measured by car purchases.

The effects of equity on refinancing are robust to a variety of controls and are economically meaningful. The increase in refinancing in response to QE1 more than doubles when moving from the bottom to the top quartile of MSAs by home equity. The additional equity extracted in these high-equity MSAs is comparable to total unemployment benefits paid out in low-equity MSAs in 2009, and our estimates imply that QE1 led to almost 250,000 additional car purchases in these high-equity MSAs. Overall, these facts show that during the Great Recession, the refinancing channel of monetary policy was weakest in the regions with the worst housing and labor market conditions.

Our second set of empirical results moves beyond QE1 to provide evidence that the consequences of monetary policy vary over time. First, we show there is large variation in the cross-regional distribution of house price growth, and thus home equity, across different recessions over the past 40 years. While we have long time series for local house prices, it is more difficult to measure local refinancing activity in historical data. However, we are able to do so for the 2001 recession. Importantly, house price patterns were very different in 2001 than in 2008. In particular,

aggregate house prices grew throughout the 2001 recession, and regional house price growth varied little across regions and was mostly uncorrelated with regional unemployment. Furthermore, we show that refinancing was higher in the 2001 recession than in the 2008 recession despite similar declines in interest rates. In addition, refinancing increased most in high unemployment MSAs in 2001, whereas the opposite was true in 2008. Finally, using aggregate (rather than regional) refinancing data going back to the early 1990s, we present evidence that the aggregate refinancing response to interest rate changes varies systematically with features of the regional house price growth distribution.

In the second half of the article, we ask: what does this regional evidence imply for the aggregate consequences of monetary policy? Although our aggregate time-series results provide some evidence that regional variation in equity has aggregate implications for refinancing, our more cleanly identified cross-regional evidence is not directly informative about aggregates. This is because our main empirical results measure only relative differences across regions, so any common aggregate effects are necessarily differenced out. An analysis of aggregation and counterfactuals then requires a formal model.<sup>3</sup> Thus, we build an incomplete-markets, heterogeneous agents model with mortgage borrowers and lenders. The goals of the model are to (i) clarify the assumptions needed to arrive at aggregate policy implications from our regional evidence; (ii) explore these aggregate implications quantitatively; and (iii) clarify the channels through which the regional distribution of equity matters for these aggregate effects. While a variety of equilibrium forces might potentially lead regional and aggregate responses to rate declines to vary differentially with equity, for parsimony we focus on modeling what we view as the single most pertinent such channel in our context. In particular, our model includes lenders whose endogenous interest income, and thus consumption, is altered by borrowers' refinancing decisions.<sup>4</sup> We find that these endogenous lender consumption offsets have important aggregate implications in our model that cannot be measured in our empirical work. Nevertheless, while the

3. See [Beraja, Hurst, and Ospina \(2016\)](#) for a more extended analysis of moving from regional to aggregate inference.

4. We discuss a number of additional equilibrium channels which might make aggregate responses differ from local responses, but we argue that these forces are small and, if anything, amplify our results.

exact magnitudes vary somewhat with different model assumptions and calibrations, we always find that regional variation in equity has quantitatively important aggregate implications for monetary policy transmission.

The key model feature driving our results is the inclusion of mortgage borrowers who face house price and income risk and can refinance mortgages and extract housing equity by paying a fixed cost. This implies refinancing decisions that follow threshold rules around some inaction region, in the spirit of [Arrow, Harris, and Marschak \(1951\)](#), [Barro \(1972\)](#), or [Sheshinski and Weiss \(1977\)](#). Households must satisfy a collateral requirement to refinance, so when interest rates fall, those with substantial equity can reduce their interest rate while extracting equity, whereas those currently underwater would need to put up additional cash. Hence, when interest rates fall, many households with positive equity refinance and further increase consumption by extracting equity, whereas almost no households with negative equity do. This leads to consumption responses to interest rate cuts that are highly convex in equity because households that are mildly underwater exhibit the same zero response as those substantially underwater, whereas households with substantial positive equity exhibit much stronger consumption changes than those with mildly positive equity. This convexity then implies that changing the distribution of equity affects the economy's response to rate declines. Thus, although the model includes many quantitatively realistic features and is rich enough to capture key aspects of the data shown in the first part of the article, it delivers transparent intuition for why the refinancing channel depends crucially on the distribution of equity.

Our first quantitative results focus on the consequences of interest rate cuts in a benchmark economy that matches the joint distribution of housing equity and income observed in 2008. To discipline this exercise, we pick baseline parameters so our model matches the regional effects of QE1 documented in the first part of the article and then compute the aggregate effects of this policy. We find that a decline in interest rates of the magnitude observed after QE1 modestly raises aggregate spending. This implies that the spending offset coming from lenders in equilibrium is not one-for-one, which occurs because our model features an important role for cash-out activity in determining spending. Households accumulate equity over time and periodically pay a refinancing cost to access this equity. Furthermore, since borrowers are more

liquidity constrained than lenders, equity extraction increases spending on net. When interest rates decline, refinancing and equity extraction are accelerated and aggregate spending rises. However, under 2008 economic conditions, this aggregate spending effect is quantitatively small. As in our empirical analysis, we also find that monetary stimulus mainly flows to regions that are doing relatively well and thus amplifies cross-regional consumption inequality.

In contrast, when we simulate the response to the same change in interest rates under economic conditions in 2001, we find very different effects: monetary policy generates much larger aggregate spending responses, and it actually mildly reduces cross-regional inequality. These conclusions depend importantly on the fact that in 2001, aggregate house price growth is positive and local house price growth is essentially uncorrelated with local economic conditions.

Then we ask: what can policy makers do in situations like 2008, when monetary policy's effectiveness through the refinancing channel is hindered? We show that targeted debt reduction and relaxation of collateral constraints for refinancing can potentially amplify the stimulative effects of monetary policy and also reduce the trade-off with inequality. Policies along these lines were implemented during the Great Recession (though only after the large drop in interest rates we study) through the Home Affordable Modification and Refinance Programs (HAMP and HARP). Although our modification policies are intentionally stylized and more aggressive than these actual policies, our results show that strong mortgage market interventions can successfully complement monetary policy.

It is useful to more broadly discuss the practical implications of our results for policy making. Central banks typically have no mandate to reduce spatial inequality or eliminate regional business cycles, and it is not clear that monetary policy has the tools necessary to address such concerns even if they wanted to. However, monetary policy makers do care about aggregates. Our results highlight that the aggregate impact of monetary policy depends importantly on the regional distribution of housing equity. Furthermore, even if central banks focus only on aggregate stabilization, their actions will nevertheless have consequences which vary across space. Such regional effects may in turn be important for the design of national fiscal policy, which is often the policy instrument of choice for stabilizing regional business cycles. State

and other local authorities also have an obvious interest in forecasting the local consequences of monetary policy. Thus, even if central banks themselves only use regional information to more precisely estimate aggregate effects of their actions, there are still many additional reasons to understand the local implications of monetary policy.

We note that although our empirical analysis focuses mostly on QE1 (since it provides a relatively well-identified shock to mortgage rates), our conclusions also apply to conventional monetary policy. Because conventional expansionary monetary policy also lowers mortgage rates, it will have similar time-varying interactions with the equity distribution.<sup>5</sup>

We study the distribution of equity and inequality across regions rather than across households within regions for similar practical reasons. Changes in the individual equity distribution in our data are mostly driven by regional house price movements, and regional house price data are more readily available at high frequencies than data on individual equity, so regional distributions are a more practical input for policy making.<sup>6</sup> In addition, inequality within regions is largely determined by income and wealth heterogeneity rather than by the refinancing channel of monetary policy.

## II. RELATED LITERATURE

Our work is related to much existing research. We depart from the New Keynesian literature, which typically assumes frictionless household capital markets with one-period borrowing. In reality, the bulk of household borrowing occurs through the mortgage market, which features collateral requirements and long-term fixed nominal payments that can only be refinanced at some cost. Together, these features give rise to what we call the “refinancing channel” of monetary policy, which we show depends on the time-varying distribution of housing equity in the economy.

5. See, for example, [Gertler and Karadi \(2015\)](#) or [Wong \(2016\)](#). There is time variation in the pass-through from short rates to long-term bond yields (e.g., [Hanson, Lucca, and Wright 2017](#)) and from long-term yields to mortgage rates (e.g., [Fuster, Lo, and Willen 2017](#)), but we find no systematic relationship of this pass-through with house price growth, a proxy for equity.

6. Equity also varies due to leverage differences at origination, differential equity extraction and amortization, and subregional house price shocks, which is why we use equity rather than house price growth in our analysis when available.

We contribute to the growing literature arguing that the economy exhibits time-varying responses to aggregate shocks, which depend on the microeconomic distribution of agents.<sup>7</sup> The most closely related of these papers is [Berger et al. \(2018\)](#), who argue that increases in household leverage during the housing boom contributed to the large decline in spending when house prices subsequently crashed. Interestingly, we show that these same leverage patterns hampered monetary policy's ability to stimulate the economy.

We are not the first to model monetary policy transmission through the mortgage market. [Rubio \(2011\)](#), [Garriga, Kydland, and Sustek \(2017\)](#), and [Greenwald \(2016\)](#) also model this channel but use a representative borrower. This means their models have no role for the distribution of housing equity, which is at the heart of our article. Our focus on realistic modeling of household borrowing and how it interacts with heterogeneity in the economy parallels many of the themes in [Auclert \(2017\)](#), who argues that the covariance of the marginal propensity to consume with interest rate exposure across agents matters for aggregate consumption responses to rate changes. His analysis abstracts from refinancing, which we show interacts with the time-varying distribution of housing equity. [Wong \(2016\)](#) uses a model closer to our own, but in partial equilibrium, and she focuses on how aging affects monetary policy. Since the age distribution changes slowly across time, age effects are more relevant for cross-country comparisons and long-run trends than for shorter-run changes in the refinancing channel of monetary policy. [Guren, Krishnamurthy, and McQuade \(2018\)](#) and [Hedlund et al. \(2017\)](#) build general equilibrium models with heterogeneity but use them to study alternative mortgage designs and housing market liquidity, respectively.

On the empirical front, [Fuster and Willen \(2010\)](#) measure effects of QE1 on the primary U.S. mortgage market. They emphasize differential effects on borrowers with different creditworthiness, while we emphasize regional disparities. [Di Maggio, Kermani, and Palmer \(2016\)](#) study refinancing responses to quantitative easing and replicate our facts at the state level, but their focus is on the time-varying composition of Fed asset purchases and their effects on conforming and nonconforming

7. See, for example, [Caballero and Engel \(1999\)](#), [Vavra \(2014\)](#), [Berger and Vavra \(2015\)](#), and [Winberry \(2016\)](#).

loans. Our empirical patterns in the QE1 episode are similar to those documented by [Caplin, Freeman, and Tracy \(1997\)](#) for the 1990 recession using data from one bank. We use more representative data over a longer time period and present a model that allows us to analyze aggregate implications and counterfactuals. Our results on spending effects of mortgage payment reductions and cash-out activity are in line with related findings by [Bhutta and Keys \(2016\)](#), [Di Maggio et al. \(2017\)](#), [Agarwal et al. \(2017b\)](#), and [Abel and Fuster \(2018\)](#). There is also a growing literature using aggregate VARs to document that responses to monetary policy vary with regional housing markets ([Fratantoni and Schuh 2003](#)) and household debt ([Alpanda and Zubairy 2018](#)).

Finally, a large literature studies a “credit channel” of monetary policy, where changes in collateral values amplify output responses to rate changes.<sup>8</sup> This channel is complementary but distinct from ours, as it arises from monetary policy changing collateral values which, in turn, affect economic activity. In contrast, we take the distribution of collateral at a point in time as given and show that it affects the transmission from interest rates to spending. We think both channels are important, and exploring their interaction is an interesting area for future work.

### III. DATA

We briefly describe our primary mortgage-related data here. The [Online Appendix](#) provides additional details as well as discussion of other data used in our analysis.

Our main local refinancing measures come from Equifax’s Credit Risk Insight Servicing McDash (CRISM) data set. This data set merges McDash mortgage-servicing records (from Black Knight Financial Services) with credit bureau data (from Equifax) and is available beginning in 2005. The structure of the data set makes it possible to link multiple loans by the same borrower together, something that is not possible with mortgage-servicing data alone. This allows us to measure refinancing activity much more accurately than can be achieved with previous data. Since we know both the outstanding amount of the old loan (as well as any second liens) and the new loan, we can measure the

8. For example, [Iacoviello \(2005\)](#) shows that adding collateral constraints on housing to a financial accelerator model like that in [Bernanke, Gertler, and Gilchrist \(1999\)](#) amplifies the effects of rate changes.

dollar amount of equity removed (or “cashed out”) from the home during refinancing. CRISM covers roughly two-thirds of the U.S. mortgage market during the period we study.

We also use CRISM data to measure borrowers’ home equity. We define home equity as one minus the household’s combined loan-to-value (CLTV) ratio, which we estimate for each household by adding balances of first mortgages and any second liens and dividing by estimated property values. We estimate property values using appraisal values at loan origination, which we then update using location-specific house price indexes from CoreLogic. Our preferred summary statistic for local equity conditions is the equity of the median borrower in a location.<sup>9</sup> This statistic  $E_{j,t}^{med}$  varies across MSAs  $j$  and time  $t$ . We particularly emphasize  $E_{j,Nov2008}^{med}$ : median equity in November 2008, just prior to QE1.

We supplement our analysis of refinancing activity using data from the Home Mortgage Disclosure Act (HMDA). For each mortgage application, HMDA data reports a variety of loan characteristics, including loan purpose (purchase or refinance) and property location. HMDA data have broader coverage over a longer time period than CRISM data, which allows us to extend our analysis to the 2001 recession. However, it does not contain information on outstanding loans, which is necessary for measuring the equity distribution and equity removed during refinancing. In the [Online Appendix](#), we show that regional refinancing patterns after QE1 are nearly identical in HMDA and CRISM data.

#### IV. THE REFINANCING CHANNEL ACROSS REGIONS: EVIDENCE FROM QE1

This section documents several facts relating regional heterogeneity in housing equity to the refinancing channel. We use an event study of the interest rate decline following QE1 to show (i) mortgage originations increased substantially after QE1, mostly driven by households refinancing existing mortgages rather than by an increase in new purchases; (ii) refinancing activity and equity extraction were higher in MSAs where homeowners had more equity (which were also locations where unemployment was lower) prior to QE1; and (iii) car purchases increased the most after QE1

9. We compute medians weighting borrowers by outstanding mortgage balances. Repeating our analysis using the fraction of borrowers with CLTV above 0.8 or above 1 yields very similar results.




FIGURE I

Mortgage-refinancing Activity in the United States over 2000–2012

Figure shows monthly average of Mortgage Bankers Association (MBA) Refinancing Index (seasonally adjusted; March 1990 = 100) and the 30-year fixed-rate mortgage rate (relative to five-year moving average), also from MBA.

for individuals who removed equity when refinancing and in MSAs with the largest refinancing response.

#### IV.A. Aggregate Trends in Mortgage Activity around QE1

Figure I shows the monthly Mortgage Bankers Association Refinance Index from 2000 to 2012 (solid line) and the difference between the 30-year fixed-rate mortgage (FRM) rate in month  $t$  and the average of the 30-year mortgage rate over the prior five years (dashed line). Negative values mean mortgage rates in a given month are low relative to previous years, giving many borrowers an incentive to refinance. Several points stand out in Figure I. First, there is a strong negative relationship between refinancing and mortgage rates: the correlation between the two series is  $-0.77$ . Second, mortgage rates fell and refinancing activity expanded sharply when QE1 was announced in November 2008, marked as a vertical line in the figure. The Online Appendix shows that similar patterns hold in HMDA data and that the increase in mortgage originations after QE1 was almost entirely refinancing rather than new purchase mortgages. For this reason, we focus our analysis on refinancing.

We focus on QE1 because it was largely unexpected and followed by such a sharp drop in mortgage rates, and because our

CRISM data begin in 2005. Although high-frequency event studies show that both mortgage rates and applications reacted strongly to QE announcements (Fuster, Lo, and Willen 2017), it is of course likely that other factors also contributed to the low rates following QE1. This is not a problem for us because we are more generally interested in the transmission of interest rate drops to refinancing and household consumption, and monetary policy is one key driver of such interest rate drops. Thus, our focus is also not QE-specific: the refinancing channel of monetary policy can potentially operate whenever monetary policy moves mortgage rates. While the refinancing boom after QE1 was larger than at any time since mid-2003, it was stronger still in 2001–2003 when falling rates were coupled with broad-based house price appreciation in most locations. Therefore, we often contrast the effects of the refinancing channel in 2008–2009 with the effects in 2001–2003.

It also bears noting that the beginning of QE1 is separated in time from other housing market policies implemented in response to the Great Recession. Specifically, the Home Affordable Modification and Refinance Programs (HAMP and HARP) were announced in March 2009, with the goal of alleviating the collateral friction we study (which we return to in Section VII) but for various reasons (such as limited participation by servicers) had a very slow start. In particular, HARP only started having large effects on refinancing volumes in 2012 (Agarwal et al. 2017b), well after our study window.<sup>10</sup> Furthermore, any debt reduction policies around the time of our sample would likely reduce our effects of interest since they would have larger effects in low-equity MSAs.

To get a sense of the potential effects of refinancing on borrowers' disposable resources during the Great Recession, we note that in the CRISM data over the first half of 2009, the median rate on the old loan was 6.125%, and the median rate on the new (refinance) loan was 4.875%. The average balance of the first-lien mortgage being refinanced was \$206,000, so that, leaving the balance unchanged and assuming a 30-year FRM, the monthly

10. Agarwal et al. (2017b) show that refinancing spurs spending and that this channel was strengthened by HARP's reduction of collateral frictions, in line with the mechanism we emphasize. Another major policy intervention was that Fannie Mae and Freddie Mac were placed in federal conservatorships in September 2008, but this did not by itself lead to a drop in mortgage rates or a refinancing boom; it did assure that credit supply continued relatively uninterrupted, at least for conforming mortgages (Frame et al. 2015).

payment would decrease by at least \$160.<sup>11</sup> If we discount this at 5% a year over seven years (roughly the average life span of a mortgage) then the present value of pretax savings is \$11,400 for monthly payments and \$15,000 for interest payments. The latter is larger since the lower rate leads to faster amortization. In addition to lowering the interest rate, many borrowers also increase the balance of their loan by withdrawing some of their equity. Over 2009:H1, the mean and median equity withdrawal in our data are \$25,000 and \$7,400, respectively.

#### *IV.B. Regional Variation in Equity Distributions Prior to QE1*

Throughout the article, we use MSAs as our measure of “regions.” We begin by showing that equity distributions evolved very differently across MSAs between 2007 and 2008. [Figure II](#) shows the distribution of household housing equity in two different time periods for five MSAs: Chicago, Las Vegas, Miami, Philadelphia, and Seattle. These are examples of MSAs that had house price declines from 2007 to 2008 that were large (Miami and Las Vegas), medium (Chicago), and small (Philadelphia and Seattle).<sup>12</sup> Panel A shows the housing equity distribution for these MSAs in January 2007, just prior to the nationwide house price decline. For all five MSAs, housing equity distributions are quite similar. As noted above, we often summarize the distribution in each MSA  $j$  at a point in time using the equity of the median borrower  $E_{j,t}^{med}$ . In January 2007,  $E_{j,t}^{med}$  in most of these MSAs is between 0.3 and 0.4. The equity of the median borrower in Las Vegas is a bit lower (roughly 0.23) since house prices there starting falling before 2007.

Panel B shows that by November 2008, when QE was announced, there was large variation in equity distributions across MSAs. Between early 2007 and late 2008, the equity distribution in places like Las Vegas and Miami shifted dramatically relative to places like Philadelphia and Seattle. By November 2008,  $E_{j,t}^{med}$  was around  $-0.17$  in Las Vegas and 0 in Miami. Conversely,  $E_{j,t}^{med}$  in Philadelphia and Seattle was around 0.25–0.3, so the median borrower in these MSAs still had substantial equity. The equity of the median borrower correlates strongly with other moments of

11. In reality the decrease would typically be larger since the old monthly payment is based on the higher original balance.

12. [Online Appendix](#) Table A.1 shows descriptive statistics for all 381 MSAs in our analysis.




FIGURE II

Distributions of Borrowers' Equity in Their Homes across Five MSAs

Figure shows the cumulative distribution of borrower equity in five illustrative MSAs in January 2007 and November 2008. Equity is measured for each household using CRISM data as the estimated current house value minus total current mortgage debt, divided by estimated current house value (i.e., equity =  $1 - CLTV$ ). Distributions are weighted by the mortgage balance.

the equity distribution. For example, 50% of borrowers in Miami and 70% of borrowers in Las Vegas had negative equity in November 2008, while only 6–10% had negative equity in Philadelphia and Seattle.

The [Online Appendix](#) explores many more results that reinforce the patterns in [Figure II](#). Specifically, we show the distribution of  $E_{j,t}^{med}$  across all 381 MSAs in January 2007 and November 2008 to highlight that the cross-regional heterogeneity in [Figure II](#) is representative. We also show similar patterns for the distribution of individual equity rather than  $E_{j,t}^{med}$  to illustrate that focusing on median equity is not essential for our conclusions. We show the relationship between equity, unemployment changes, and house price growth from January 2007 to November 2008. Over this period, differential house price declines across MSAs were the main driver of differences in  $E_{j,t}^{med}$ . On average, a 10% decline in house prices from January 2007 to November 2008 is associated with an 8.3 percentage point lower  $E_{j,Nov2008}^{med}$ . We cannot measure local equity before 2005, but this relationship between house price growth and equity will allow us to use regional variation in house price growth to proxy for regional variation in housing equity in earlier periods.

Finally, we document that MSAs with the largest increases in local unemployment rates also had the lowest  $E_{j,Nov2008}^{med}$ . This is unsurprising because house price declines were associated with weakening labor markets during this period ([Charles, Hurst, and Notowidigdo 2013](#); [Mian and Sufi 2014](#)), but it is important for interpreting the cross-regional effects of monetary policy, since we will now show that refinancing activity responded least to QE1 in the locations with the least home equity.

#### IV.C. Regional Variation in Mortgage Activity around QE1

We now show that in the months after QE1 was announced, refinancing activity was much higher in regions with more home equity and lower unemployment. To facilitate the exposition of our results, we divide all MSAs into quartiles based on  $E_{j,Nov2008}^{med}$ .<sup>13</sup> [Figure III](#) shows refinancing activity over time for MSAs in the top and bottom quartiles of  $E_{j,Nov2008}^{med}$ . The bottom

13. Quartiles are population weighted using 2008 numbers from the census. This ensures that there are the same number of people within each quartile. [Online Appendix A.1](#) lists the specific MSAs within each of the  $E_{j,Nov2008}^{med}$  quartiles.




FIGURE III

Mortgage Refinance Activity 2008–2009 in Top and Bottom Quartile of MSAs Defined by Median Borrower Equity in November 2008

Panel A shows monthly refinance propensities in CRISM, defined as the dollar amount of refinance mortgage originations divided by outstanding mortgage amounts in the prior month. Calculations are done over MSA quartile groups for the highest and lowest  $E_{j,Nov2008}^{med}$  quartiles. Panel B shows the cumulative difference between the two groups, after subtracting each group's average refinancing propensity from January to November 2008. Vertical lines show the month of the QE1 announcement (November 2008).

quartile of  $E_{j,Nov2008}^{med}$  includes MSAs like Las Vegas where the median mortgage borrower was underwater. The top  $E_{j,Nov2008}^{med}$  quartile includes MSAs like Seattle where most borrowers had sufficient equity to refinance.

Panel A shows monthly refinancing propensities from January 2008 through December 2009. Refinancing propensities are higher throughout in the high-equity quartile, but they evolve similarly between high- and low-equity MSAs up to November 2008. After QE1, refinancing activity jumped—but it jumped much more in the high-equity MSAs relative to the low-equity MSAs.<sup>14</sup>

Panel B shows the cumulative difference between the two groups, after subtracting each group’s average refinancing propensity from January to November 2008 to remove the initial level difference. Prior to QE1, the cumulative difference is essentially flat at zero, reflecting the parallel pretrend in Panel A. After QE1, a sharp difference emerges, eventually leading to a cumulative refinancing propensity about 5 percentage points larger in the high-equity MSA group than in the low-equity MSA group. This is a substantial difference, since the cumulative refinancing propensity in the low-equity group is only 7% over the entire year 2009.

While Figure III shows a clear difference in refinancing responses to QE1 in high- and low-equity MSAs, one might be concerned that this difference is driven by other factors that vary across these MSAs. We thus complement these figures with difference-in-differences style regressions, which allow us to control for additional local factors and assess statistical significance. Specifically, we estimate:

$$\begin{aligned}
 Refi_{j,t} = & \alpha_j + \alpha_t + \beta(E_{j,Nov2008}^{med} \times postQE) \\
 (1) \quad & + \Gamma(X_{j,Nov2008} \times postQE) + \varepsilon_{j,t},
 \end{aligned}$$

14. The jump happens in January/February (rather than December) because CRISM measures originations, not applications, and there is a delay of one to three months between when a mortgage application is initially made and when the actual mortgage origination takes place due to the underwriting process. As Fuster, Lo, and Willen (2017) document, loan processing times increased following the QE1 announcement, but based on HMDA data with exact application and origination dates, we find little differential increase between high- and low-equity MSAs. In Online Appendix Figure A.5, we use the HMDA data to show that applications jumped immediately after the announcement of QE1, and more so in high-equity MSAs.

where  $Ref_{j,t}$  is the monthly refinancing propensity in each MSA over the six months prior to QE1 and the six months after QE1,  $\alpha_j$  and  $\alpha_t$  are MSA and time fixed effects, and  $postQE$  is an indicator variable that equals 1 for the six months after QE1. We use February 2009 as the start of the post-QE-announcement period because there is a lag between the time one applies for a mortgage and when it is originated, as discussed in note 14.  $X_{j,Nov2008}$  is a vector of local controls including changes in the unemployment rate between January 2007 and November 2008, changes in local income between January 2007 and November 2008, average borrower FICO score, average outstanding interest rate on mortgages, average loan age, average mortgage balance, and local ARM, jumbo, GSE, and privately securitized shares of loans. All the latter variables are measured in November 2008. We also include local age, education, and homeownership controls measured using the 2008 American Community Survey. Regressions are run including one control at a time as well as jointly including all controls.

The results shown in Table I reinforce the patterns found in Figure III, but some results are worth highlighting. First,  $\beta$  is always positive and highly statistically significant, indicating that the patterns in Figure III are robust to many detailed local controls. Importantly, all controls are interacted with  $postQE$  so that the responsiveness of refinancing to interest rates can vary with these observable characteristics, and all regressions include MSA fixed effects, which absorb any permanent differences in refinancing across MSAs due to unobservables. Adding the average FICO score of mortgage borrowers (interacted with  $postQE$ ) to the regression reduces the coefficient on equity by almost half, but average FICO scores are themselves endogenous to changes in local equity (since underwater borrowers are more likely to default); therefore, we view the fact that equity remains strongly significant as underscoring its importance in explaining differences in refinancing. Adding all additional controls at once further reduces  $\beta$ . Again, this is to be expected since a linear combination of these variables is very highly correlated with median equity. Nevertheless, equity remains individually significant. Given that the exact magnitude of equity effects varies with controls, we use a range of estimates for this relationship in our theoretical model.

In the second half of the article, we explore the aggregate implications of these cross-regional refinancing patterns. In doing so, one important question is whether these relationships weaken

TABLE I  
THE RESPONSIVENESS OF LOCAL REFINANCING ACTIVITY TO EQUITY AND OTHER LOCAL CHARACTERISTICS AROUND QE1

	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
$E_{Nov2008}^{need} \times postQE$	1.711*** (0.232)	1.161*** (0.258)	1.530*** (0.288)	0.920*** (0.237)	1.088*** (0.115)	1.856*** (0.233)	1.694*** (0.186)	0.483*** (0.184)
$\Delta UR_{Jan07-Nov08} \times postQE$		-0.0911*** (0.0188)						-0.0511*** (0.0131)
$\Delta Income_{2008-09} \times postQE$			2.123* (1.233)					-1.028 (0.776)
$FICO \times postQE$				0.0107*** (0.00101)				0.00876*** (0.00180)
Current int. rate $\times postQE$					-1.688*** (0.117)			-0.812*** (0.210)
Loan age $\times postQE$					-0.0229*** (0.00369)			-0.0326*** (0.00521)
Jumbo share $\times postQE$					-1.843*** (0.293)			-1.238*** (0.409)
Average balance (nonjumbo) $\times postQE$					-0.218*** (0.0315)			-0.231*** (0.0881)
ARM share $\times postQE$						2.269*** (0.496)		-0.188 (0.398)
GSE share $\times postQE$						0.954*** (0.240)		-0.305* (0.170)
Private sec. share $\times postQE$						-2.112*** (0.616)		0.190 (0.534)

TABLE I  
(CONTINUED).

	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
Demographics $\times$ <i>postQE</i>	N	N	N	N	N	N	Y	Y
MSA fixed effects	Y	Y	Y	Y	Y	Y	Y	Y
Month fixed effects	Y	Y	Y	Y	Y	Y	Y	Y
Adj. $R^2$	0.87	0.87	0.87	0.88	0.90	0.88	0.89	0.90
Adj. $R^2$ (within)	0.18	0.22	0.19	0.28	0.35	0.25	0.30	0.38
Observations	4,572	4,572	4,572	4,572	4,572	4,572	4,572	4,572

Notes: Table shows results from regressions of monthly refinancing propensities in 381 MSAs from August 2008 to July 2009, measured in CRISM, on median equity in each MSA interacted with a dummy "postQE" that equals 1 for the period February–July 2009, and other variables also interacted with postQE. Demographic controls in columns (7) and (8) are location-specific shares of individuals with different years of education: 12,13–15,16, >16 (<12 is omitted), shares of individuals with ages: 31–45, 46–60, >61 (21–30 is omitted), homeowner shares, and the share of households with mortgages, from the ACS. Each of these demographic controls is interacted with postQE to allow for differential responses to rate declines. All regressions also include MSA and month fixed effects. For reference, the average monthly refinancing propensity over August 2008–January 2009 was 0.4%, while over February–July 2009 it was 1.2%. Descriptive statistics of explanatory variables are provided in Online Appendix Table A-1. MSAs are weighted by their 2008 population. Robust standard errors (clustered by MSA) are in parentheses. Significance: \*  $p < .1$ , \*\*\*  $p < .01$ .

with the level of aggregation due to equilibrium forces. While these regressions all use MSAs as the measure of regions, the [Online Appendix](#) repeats the same analysis instead using states. Unsurprisingly, standard errors are larger since we only have 50 instead of 381 observations, but estimates of the effects of state-level equity on state-level refinancing are all quantitatively similar and statistically indistinguishable from the MSA-level estimates shown in [Table I](#). This provides some evidence in support of a simplifying assumption in our structural model, namely, that the demand for refinancing after rate declines varies with equity shocks in the same way at all levels of geographic aggregation.<sup>15</sup>

One might be concerned that our results could reflect relatively tighter credit supply in low-equity locations in the period after QE1. However, consistent with results in [Hurst et al. \(2016\)](#), the [Online Appendix](#) shows there is little variation in mortgage rates across MSAs and that rates fell as much in low-equity locations as in high-equity locations after QE1. This suggests that lower refinancing rates in low-equity locations are not driven by higher borrowing costs. This likely reflects the fact that during this time period, the mortgage market consists almost entirely of loans whose default risk is insured by GSEs, which do not vary their pricing with regional default risk (again see [Hurst et al. 2016](#)).

While we focus on effects of CLTV constraints, borrowers must also satisfy payment-to-income (PTI) constraints to refinance. During the QE1 episode, house price declines are highly correlated with increases in unemployment, so it is possible our results might be driven by PTI rather than CLTV constraints. [Table I](#) shows that conditional on local equity levels, MSAs with larger increases in unemployment saw moderately smaller increases in refinancing, but that equity effects remain independently very large. Similarly, controlling directly for income also has little effect on our coefficient of interest. The [Online Appendix](#) further shows that the distribution of PTI for newly originated loans in 2009 is very similar in high- and low-equity MSAs and exhibits no bunching around institutional constraints, in contrast to substantial bunching and spatial variation in the distribution of CLTVs. This strongly suggests that our results are primarily driven by spatial variation in equity rather than PTI constraints.

15. The MSA-level cash-out and auto-spending results shown in the next section are also similar at the state level.

Collectively, the results from [Figure III](#) and the various robustness results provided in the [Online Appendix](#) show there were large regional differences in refinancing activity in response to QE1. Regions with the least equity were the least responsive to QE1 in terms of subsequent mortgage-refinancing activity.

#### IV.D. Regional Variation in Equity Extraction and Spending around QE1

To what extent do these spatial differences in refinancing activity lead to differences in spending? Unfortunately, local spending data are extremely limited, but we provide evidence on this front in two ways. First, we explore the extent to which households removed equity from their home when refinancing. Prior research has shown that households typically spend a large amount of such “cash-outs” on current consumption and home improvements.<sup>16</sup> Second, we use R.L. Polk data on new car purchases at the MSA level as one measure of local spending, as in [Mian, Rao, and Sufi \(2013\)](#).

[Figure IV](#) shows the amount of equity removed during refinancing for the top and bottom quartile MSAs by  $E_{j,Nov2008}^{med}$ . Panel A shows dollar amounts per month, and Panel B shows the cumulative difference between the two groups, after subtracting each group’s average cash-out amounts from January to November 2008. The total amount of equity removed during the refinancing process sums over households who removed no equity, those who put equity into their home, and those who extracted equity. On net, borrowers remove equity during the refinancing process in both high- and low-equity locations. At all points in time, there is more equity removal in high-equity locations, but trends evolve similarly prior to the QE1 announcement. After QE1, equity removal increases substantially in the high- $E_{j,Nov2008}^{med}$  locations relative to the low- $E_{j,Nov2008}^{med}$  locations.

Summing across all MSAs in the top equity quartile, about \$23.8 billion of equity was cashed out during refinancing in the six months after QE1 (January–June). Conversely, for the MSAs in the bottom equity quartile, only \$10.9 billion of equity was cashed out. However, some of this \$12.9 billion difference reflects the continuation of differential extraction levels prior to QE1. Panel

16. See [Brady, Canner, and Maki \(2000\)](#), [Canner, Dynan, and Passmore \(2002\)](#), [Hurst and Stafford \(2004\)](#), and [Bhutta and Keys \(2016\)](#).




FIGURE IV

Cash-Out Refinancing in Top and Bottom Quartiles of MSAs by Median Borrower Equity in November 2008

Panel A shows total cash extracted during refinancing in the top and bottom MSA quartiles by  $E_{i,t,Nov}^{med}$ . Panel B shows the cumulative difference between the two groups, after subtracting each group's average cash-out amounts from January to November 2008. Since CRISM data does not cover the whole mortgage market, we scale up dollar amounts in CRISM for this figure; see [Online Appendix A.2.3](#) for details. Vertical lines show the month of the QE1 announcement (November 2008).

B shows the cumulative difference in cash-out amounts over 2009 between the two MSA groups—after subtracting each group’s pre-QE averages—amounted to around \$8 billion.<sup>17</sup>

Is an \$8 billion difference in equity extraction across regions caused by QE1 a large number? Since this number comes from a cross-regional calculation, which differences out any aggregate effects, it should not be interpreted as the effect of QE1 on aggregate equity extraction or compared to the overall size of the recession. In the second half of the article we use a model to infer aggregate effects from our cross-regional evidence, but for now it is more relevant to compare the \$8 billion cash-out difference to differences in the size of the recession across regions. Using Bureau of Economic Analysis (BEA) data, we find that \$8 billion is around 10% of the differential spending change from 2008 to 2009 between the two MSA groups.<sup>18</sup> This effect is both large and similar in size to the effects in our model. It is also useful to compare these numbers to other stabilization programs. Unemployment benefit payments in 2009 totaled around \$16 billion in the lowest-equity MSAs. Thus, \$8 billion is similar in magnitude. However, our results show it differentially went to the regions with the lowest instead of highest unemployment rates.<sup>19</sup> Dividing \$8 billion by the number of households in the highest equity quartile implies that QE1 increased potential spending per household in those locations by roughly \$280. This is similar in size to tax stimulus

17. Regressing MSA-level cash-out amounts on group dummies interacted with a *post-QE* dummy (with standard errors clustered by MSA) we get an estimate of this cumulative difference of \$7.95 billion with a standard error of \$3.11 billion. Our equity extraction measure does not include HELOC draws. Unlike cash-out refs, HELOC balances can be adjusted without closing costs, and interest rates are usually variable. This mutes incentives to respond to long-term rate declines. Nevertheless, our \$8 billion could be overstated if high-equity MSAs extract equity by refinancing while low-equity MSAs do so through HELOCs. However, using quarterly FRBNY Consumer Credit Panel data, HELOC balances grew more in high-equity than low-equity MSAs over 2008–2009, and differentially increased in high-equity locations by roughly \$4 billion after QE1. So including HELOCs would increase the differential QE effects on equity extraction to roughly \$12 billion.

18. Total GDP in low-equity MSAs fell by \$113.5 billion more than total GDP in high-equity MSAs between 2008 and 2009. Scaling these differences by the aggregate share of consumption in GDP of 68% delivers  $0.104 = \frac{8}{0.68 \times 113.5}$ .

19. Unemployment benefit payments are only reported at the state level by the Department of Labor, but we apportion state-level benefits payments to individual MSAs using each MSA’s share of total state unemployment. This calculation implies the lowest-equity MSAs received \$16.3 billion in unemployment benefits payments in 2009 and \$9.6 billion in 2008.

payments received by households in the recession and suggests that QE1 had cross-regional effects similar to sending an extra tax rebate only to locations that were already doing relatively well.

The [Online Appendix](#) also shows results from a regression similar to [equation \(1\)](#) but with monthly equity removed (relative to the outstanding balance) as the dependent variable. We refer to this variable as the cash-out share. Echoing the results in [Figure IV](#), we find a positive relationship between  $E_{j,Nov2008}^{med}$  and the cash-out share after QE1 that is highly significant and robust to a variety of additional controls. We also show that high-equity places extract more equity even after conditioning on the frequency of refinancing. That is, the patterns in [Figure IV](#) are not driven just by the differential refinancing propensities shown in [Figure III](#). To show this, we add monthly refinancing propensities as separate controls in our regression. We find that both the coefficient on  $E_{j,Nov2008}^{med} \times postQE$  and on the monthly refinancing propensity are positive and strongly significant. Hence, low- $E_{j,Nov2008}^{med}$  MSAs both refinanced less and removed less equity, conditional on refinancing. This is intuitive, since these places indeed have less equity to remove when refinancing.

Because prior research has shown tight links between equity removal and spending, these results suggest that locations with different  $E_{j,Nov2008}^{med}$  had different spending responses to QE1. However, differences in the marginal propensity to consume could potentially lead consumption to respond more to QE1 in low-equity regions despite smaller refinancing responses. In particular, it could be the case that instead of spending extracted home equity, households in high-equity MSAs used it to pay down other (higher-interest) nonhousing debt. However, as a robustness exercise in the [Online Appendix](#), we use FRBNY Consumer Credit Panel data to show that average nonhousing debt per person actually modestly increased in high-equity MSAs relative to low-equity MSAs after QE1. This suggests that borrowers in those MSAs used withdrawn equity for spending, rather than to pay down existing debt.

We now show this more directly using auto sales data from Polk. [Figure V](#), Panel A shows total monthly auto sales in the top and bottom  $E_{j,Nov2008}^{med}$  groups. A few things stand out. First, the trend in auto sales was very similar in the high- and low-equity quartiles prior to QE1. In both groups, new auto sales fell rapidly throughout 2008. Second, these trends remained parallel through February 2009. This is not surprising since refinancing




FIGURE V

New Auto Sales in Top and Bottom Quartiles of MSAs Defined by Median Borrower Equity in November 2008

Figure shows the total volume of new car purchases in the top and bottom MSA quartiles by  $E_{i,Nov}^{med}$  using R.L. Polk data. Panel A shows total monthly car purchase volumes, summed over MSAs in each quartile. Panel B shows cumulative differences between the two groups, after subtracting from each group's series the group's average car purchases from January to November 2008. MSA groups are the same as in Figure III. The vertical line shows the month of QE1 announcement.

applications that took place in December 2008 would not result in new mortgage originations until January or February 2009. Third, and most important, after February 2009, auto sales diverge sharply between the two equity groups. On average, sales increased by 31% in March–May 2009 relative to November 2008 in the high-equity MSAs while they only increased 15% in the low-equity MSAs. This difference is economically and statistically significant, and the timing lines up perfectly with expected spending responses to QE1.<sup>20</sup> Panel B shows that cumulative differences between the groups through 2009 amount to 250,000 cars, or roughly 1.5 months of sales. It is also worth noting that these differences all occur prior to the start of the Cash-for-Clunkers program in July 2009 and so are not driven by this program.<sup>21</sup>

*IV.D.1. Household-Level Analysis of Spending after Refinancing.* Of course, high- and low-equity MSAs differ in many ways, so that observed differences in spending following QE1 could be due to factors other than mortgage refinancing and equity withdrawal. Our spending regressions include both MSA fixed effects and long-run MSA trends to control for many differences across MSAs, so any alternative explanation would need to interact at high frequencies with our QE1 event study. However, channels aside from refinancing might satisfy this requirement. For instance, mortgage defaults were higher in low- $E_{j,2008}^{med}$  MSAs, which would lower credit scores and make it more difficult to benefit from lower interest rates on car loans.

To provide direct evidence that spending effects indeed arise from refinancing, we move to CRISM data at the household level

20. The [Online Appendix](#) shows MSA-level regressions, similar to [equation \(1\)](#), but using the log of monthly new car sales as our dependent variable.  $\beta$  is positive and statistically significant even if we allow for differential time trends across locations with different equity levels. Furthermore, to directly test the link between refinancing, equity extraction, and auto sales, we add both refinancing and cash-out propensities as independent variables and find they are both correlated with stronger auto sales over this period. Once we control for equity and refinancing propensities, only the latter are significant, consistent with the hypothesis that equity only matters for spending through its effects on refinancing.

21. The start of the program can be seen as a large spike in Panel A. Although irrelevant for our regressions with MSA fixed effects, clunker shares are actually mildly negative correlated with median equity which should imply larger responses to cash-for-clunkers in low-equity regions. This correlation, together with the fact that the program pulled forward many purchases from the future, may explain why spending differences with equity disappear after July 2009.

(rather than the MSA level) and study spending responses of borrowers who refinanced at some point in 2009. The credit record component of the data includes information on each borrower's monthly auto loan balances, and we follow the literature (e.g., [Di Maggio, Kermani, and Palmer 2016](#); [Agarwal et al. 2017b](#)) in using large balance increases from one month to the next as a proxy for a car purchase. We then conduct an "event study" where we look at borrowers' propensity to purchase a car in the months around refinancing. Given our earlier analysis, we are particularly interested in how spending responses differ between cash-out and non-cash-out refinances.

[Figure VI](#), Panel A simply shows average car purchase propensities for borrowers in the months before and after completing a cash-out or non-cash-out refinance. Supporting the view that refinancing spurs spending, purchase propensities spike for both groups following the refinance, and more so for borrowers who remove equity during the process. Panel B shows monthly coefficients (and 95% confidence intervals) from a regression of the car purchase indicator on calendar-month-by-MSA fixed effects, as well as indicators of the distance in months to the time of the refinance, with month -1 as the omitted month. The results show a strong increase in car purchase propensities in the months following refinancing, with a peak after two months that is almost twice as large for cash-out as for non-cash-out refinances. Effects remain positive for several months after refinancing, and there is little pretrend prior to refinancing. While this link from refinancing to car spending is not necessarily causal (we do not have exogenous variation in refinancing propensity at the individual level), it nevertheless supports the view that refinancing in the wake of QE1 did stimulate consumer spending, and more so if the borrower also removed equity in the process. We further note that positive refinancing effects on spending are also found in work exploiting exogenous variation in access to refinancing ([Agarwal et al. 2017b](#); [Abel and Fuster 2018](#)) or payment reductions from ARM resets ([Di Maggio, Kermani, and Palmer 2017](#)).

The results in this section suggest that QE1 raised aggregate spending by borrowers (in part by inducing them to remove equity) but that regional spending responses differed with equity at the onset of QE1. Collectively, our results show that the "refinancing channel" of monetary policy interacts with the regional distribution of housing equity and that the 2008 distribution reduced the effectiveness of monetary policy by preventing it from stimulating places which needed it most.




FIGURE VI

Borrower-Level Evidence on the Response of Car Purchase Propensity to Refinancing

Panel A shows average fractions of refinancing borrowers who obtain a new car loan in each month surrounding a mortgage refinancing (in month 0), distinguishing between cash-out and non-cash-out refinancing. We identify a borrower as obtaining a new car loan in month  $t$  if their car loan balance increases by \$2,000 or more between month  $t - 1$  and month  $t$ . Panel B shows coefficients on month indicators (relative to the refinancing month, with  $-1$  as the omitted month) from a regression of the new car loan indicator on calendar-month-by-MSA fixed effects as well as months-from-refinancing indicators interacted with whether the refinancing involves cash-out. Dashed lines are 95% confidence intervals based on robust standard errors clustered at the MSA level. See [Online Appendix A.2.5](#) for additional details.

## V. THE TIME-VARYING REFINANCING CHANNEL IN THE UNITED STATES

In this section, we first show that there is substantial time variation in the regional distribution of house price growth and its correlation with unemployment changes. We then focus on the 2001 recession, which exhibits house price patterns most distinct from 2008, and show that this recession also has very different refinancing patterns. Finally, we present longer-term evidence that the refinancing response to interest rate changes depends on the regional distribution of house price growth. Together these results provide evidence that the time-varying regional equity distribution produces time-varying effects of monetary policy through the refinancing channel.

### V.A. *Regional Evidence across Time*

Because CRISM data begins in 2005, we cannot construct the housing equity data necessary to simply replicate our prior analysis in earlier recessions. However, as noted in [Section IV.B](#), house price changes and housing equity are strongly correlated in this recession. Motivated by this relationship, we now show that the cross-regional distribution of house price growth varies substantially across time. [Figure VII](#), Panel A shows average real house price growth in CoreLogic data from 1976 to 2013.<sup>22</sup>

While the large house price declines in the Great Recession stand out, there is substantial variation across time. During the 2001 recession, real house prices were growing rather than falling, and house price declines in the previous three recessions were mild. Panel B plots the standard deviation of house price growth across states in each year. Clearly, spatial variation in house price growth was unusually high in the late 1980s and in the Great Recession and unusually low during the 2001 recession.

Finally, Panel C explores relationships between state-level unemployment and house price growth, a moment that will be particularly important for determining monetary policy implications for cross-region inequality. In particular, we run a regression of one-year house price growth on state-level one-year changes in

22. State-level house prices are deflated using the CPI-U and are population weighted. We concentrate on the state-level rather than MSA-level distribution of house price growth, since MSA-level labor market data are only available starting in 1990, but patterns at the MSA (and postal code) level are similar for the mean and standard deviation.




FIGURE VII

## Changes in the Distribution of House Price Changes Across Time

Figure shows time series of the mean and standard deviation of state-level annual house price growth and of the cross-state relationship between house price growth and unemployment rate changes. Calculations are population weighted by state.

unemployment (in percentage points) interacted with annual dummies for each year from 1976 to 2013 and including year and state fixed effects so that the results are not driven by slow-moving state-level trends or aggregate unemployment changes or house price growth:

$$(2) \quad \Delta \log HP_{i,t} = \beta_t \Delta UR_{i,t} + \gamma_t + \zeta_i + \epsilon_{i,t}.$$

$\beta_t$  then measures the comovement between house prices and unemployment in the cross-section each year. Panel C shows that in the Great Recession, unemployment and house price growth were unusually negatively correlated. Again, these patterns vary across time. In the 2001 and 1980s recessions, there was basically no relationship between unemployment and house price growth.

In the following section we build a theoretical model consistent with these time-series patterns and show they imply important time-varying consequences of monetary policy. Supporting these conclusions, [Figure VIII](#) illustrates that the pass-through of




FIGURE VIII

Refinancing Propensities for High and Low Unemployment Change Quartiles, 2008 Recession and 2001 Recession

Figure shows monthly refinancing propensities for the top and bottom quartiles of MSAs by unemployment changes. Specifically, for each MSA we compute the change in unemployment between November 2007 and October 2009 (Panel A) and December 2000 to June 2003 (Panel B). Each MSA is placed into population-weighted quartiles by this measure. Refinancing propensities are computed using HMDA data on origination volumes (by month of loan application) divided by the total number of mortgages in MSA quartiles from the American Community Survey in 2008 (Panel A) or the Census in 2000 (Panel B). The vertical line in Panel A shows the month of QE1 announcement.

monetary policy through the mortgage market was much stronger in the 2001 recession than in the 2008 recession and that regional effects were also very different.<sup>23</sup> Panel A shows the time series of monthly refinancing propensities in HMDA for the lowest and highest unemployment quartile MSAs during the 2008 recession. MSAs are sorted into quartiles based on the total increase in unemployment from November 2007 to October 2009. The top (bottom) quartile experienced unemployment increases of 6.3% or more (3.8% or less) over this period.<sup>24</sup> Given the high correlation between unemployment changes and house price changes, the unemployment results in Panel A are very similar to those shown for equity quartiles in Figure III.

Panel B shows time-series patterns for monthly refinancing by unemployment quartiles during the 2001 recession. The sorting is again done by total increases in unemployment over this period. The top (bottom) quartile unemployment rate increased by 2.5% or more (1.6% or less). The refinancing patterns are very different from those shown in Panel A: during the entire period, refinancing volumes were higher in the MSAs with more rapidly rising unemployment.<sup>25</sup> Overall refinancing propensities were also dramatically higher in this earlier episode, when house prices were growing rather than shrinking (especially between mid-2002 and mid-2003). Although there was no single monetary policy “event” during this period, as the Federal funds rate instead declined gradually, it is evident from Figure I that overall mortgage rate declines relative to recent levels were similar in 2001–2003 and 2007–2009. Because the decline in mortgage rates was similar during both recessions, the fact that refinancing activity was much higher in 2001–2003 is consistent with much higher home equity during this period.

23. Since CRISM data starts in 2005, we must use HMDA data for this analysis.

24. These periods match turning points in the overall seasonally adjusted U.S. civilian unemployment rate. In the earlier episode, national unemployment increased from a low of 3.9% in December 2000 to a high of 6.3% in June 2003. In the latter episode, unemployment increased from 4.7% in November 2007 to 10.0% in October 2009.

25. Chen, Michaux, and Roussanov (2013) similarly find that over 1993–2009, refinancing activity at a point in time was higher in states with worse economic conditions. Avery et al. (2011) document lower refinancing propensities in 2010 than in 2003 using credit records data. Although these data do not allow one to measure borrower equity, state-level differences in propensities are consistent with lack of equity being an important impediment to refinancing in 2010.

### V.B. Aggregate Refinancing across Time

Of course, 2001 and 2008 are different in many ways besides their house price patterns. For instance, credit standards were likely tighter in 2008 due in part to the disappearance of non-agency securitization. In addition, all results so far have focused on how regional refinancing patterns differ with regional equity. In this subsection we provide some more systematic time-series evidence that aggregate responsiveness of refinancing to interest rate changes depends systematically on regional housing market conditions. While we also use our theoretical model to explore the aggregate implications from our cross-regional evidence, these time-series results provide more direct empirical evidence that regional housing market conditions indeed matter for aggregate refinancing.

Formally, we separately estimate the following two regressions:

$$(3) \quad \begin{aligned} Refi_t = & \omega_0 + \omega_1 Rate_t + \omega_2 \Delta HP_t + \omega_3 Rate_t \times \Delta HP_t \\ & + \omega_4 SD(\Delta HP_t) + \omega_5 Rate_t \times SD(\Delta HP_t) + \epsilon_t \end{aligned}$$

and

$$(4) \quad \begin{aligned} \Delta Refi_t = & \omega_0 + \omega_1 \Delta Rate_t + \omega_2 \Delta HP_t + \omega_3 \Delta Rate_t \times \Delta HP_t \\ & + \omega_4 SD(\Delta HP_t) + \omega_5 \Delta Rate_t \times SD(\Delta HP_t) + \epsilon_t, \end{aligned}$$

where  $Refi_t$  is the ratio of refinance mortgages with application month  $t$  (from HMDA) to the stock of outstanding mortgages in month  $t - 1$  (from the Flow of Funds), and  $\Delta Refi_t$  is the one-year change in  $Refi_t$  (i.e., between months  $t - 12$  and  $t$ ). For  $Rate_t$  in specification (3), we use a measure of the average incentive to refinance, defined as the difference between the market rate on new 30-year FRMs in month  $t$  and the average rate on outstanding mortgages in month  $t$ . The more negative this difference, the more the average borrower gains from refinancing.  $\Delta Rate_t$  in equation (4) is either the 12-month change in the market rate on new 30-year FRMs, or the 12-month sum of monthly monetary policy surprises from Gertler and Karadi (2015). These rate measures are interacted with one-year rolling average real house price growth across states ( $\Delta HP$ , as in Figure VII, Panel A) and the standard deviation of house price growth across states ( $SD(\Delta HP)$ , Figure VII, Panel B) to study how the transmission of monetary

policy to refinancing varies with the regional house price distribution. Since the required monthly HMDA data is only available beginning in 1990 and the monetary shocks series in [Gertler and Karadi \(2015\)](#) ends in 2012, the time series for this analysis is necessarily shorter than that in [Figure VII](#), but [Table II](#) shows that we can still use it to uncover fairly strong relationships between monetary policy, regional house price growth, and aggregate refinancing.

Column (1) shows that as expected, there is a strong relationship between refinance propensities at the aggregate level and the average borrower's incentive ( $\omega_1 < 0$ ). However, column (2) shows the strength of this relationship varies with prior house price growth: it is significantly stronger when house prices were growing on average ( $\omega_3 < 0$ ) and if there is more heterogeneity in house price growth across space ( $\omega_5 < 0$ ). These results are at the heart of the mechanism in this article, as the theoretical model will help clarify.

In columns (3) and (4), we repeat these regressions in one-year changes, using the change in 30-year FRM rates as the key right-hand-side variable. As rates fall, we find refinancing strongly increases. Again, this refinancing response rises with the mean and dispersion of house price growth. Columns (5) and (6) show results are similar when redoing the regression using monetary policy shocks. This specification alleviates concerns about reverse causality, although we would generally expect them to go in the opposite direction of what we find: for instance, one could imagine that as refinancing increases and aggregate demand strengthens, that would lead to an increase in interest rates. Although these regressions are not as cleanly identified as our results using regional variation around QE1, we find it encouraging that these aggregate time-series results are consistent with our model predictions.<sup>26</sup>

## VI. A MODEL OF REGIONAL HETEROGENEITY AND MONETARY POLICY

In this section, we move to a theoretical analysis of the interaction between monetary policy and regional heterogeneity that can be used to interpret our empirical results. Our goal is to clarify how the regional equity distribution affects the transmission from interest rate cuts to both local and aggregate spending through

26. Results are also similar when using only data from before 2008.

TABLE II  
AGGREGATE REFINANCING PROPENSITIES AND INTEREST RATES

Dep. var.:	$Ref_t$		$\Delta Ref_{t-12,t}$		
Int. rate measure:	Mtg. rate minus avg. outstanding (1)	(2)	$\Delta Mtg.rate_{t-12,t}$ (3)	$\Sigma_{t-12}^t Mon. pol. shocks$ (5)	(6)
Rate	-0.697*** (0.181)	-0.962*** (0.139)	-0.977*** (0.126)	-0.983*** (0.128)	-1.387*** (0.478)
$\Delta H P$		0.063*** (0.012)		0.004 (0.021)	0.007 (0.029)
Rate $\times \Delta H P$		-0.095*** (0.030)		-0.070** (0.032)	-0.248** (0.120)
SD( $\Delta H P$ )		0.116*** (0.036)		-0.076 (0.060)	-0.106 (0.084)
Rate $\times SD(\Delta H P)$		-0.178** (0.077)		-0.176* (0.092)	-0.944* (0.490)
Constant	1.003*** (0.077)	0.964*** (0.060)	-0.241** (0.113)	-0.180* (0.108)	-0.192 (0.148)
Adj. $R^2$	0.22	0.63	0.50	0.56	0.20
Obs.	222	222	258	258	258

Notes. Table shows results from regressions of monthly aggregate refinancing propensities on measures of (mortgage) interest rates. In columns (1) and (2), the interest rate measure is the mortgage rate on new 30-year FRMs (from Freddie Mac PUMS) minus the weighted-average coupon on outstanding mortgages guaranteed by Fannie Mae, Freddie Mac, and Ginnie Mae (from eMBS, available since January 1994). In columns (3) and (4), the interest rate variable is the 12-month change in the rate on new 30-year FRMs (one standard deviation = 0.78). In columns (5) and (6), the interest rate variable is the 12-month sum of monthly monetary policy surprises (the surprise in the three-month ahead futures rate) from Gertler and Karadi (2015) (one standard deviation = 0.28). Sample period: columns (1)–(2); January 1994–June 2012; (3)–(6); Jan 1991–June 2012, June 2012 is when the Gertler-Karadi series ends. Standard errors in parentheses are Newey-West (4 lags) in columns (1)–(2) and Hansen-Hodrick (12 lags) in columns (3)–(6). Significance: \*  $p < .1$ , \*\*  $p < .05$ , \*\*\*  $p < .01$ .

the refinancing channel. Because the equity distribution is time varying, we argue that this leads to situations where expansionary monetary policy provides the least stimulus to the places that need it most and thus faces a trade-off between stimulating aggregate spending and increasing cross-regional consumption inequality. Our model includes many realistic features of mortgage markets, including equilibrium effects between borrowers and lenders, but is intentionally stylized in many other dimensions, because the goal is to transparently illustrate how the refinancing channel of monetary policy interacts with the regional distribution of equity. Embedding our framework into a richer DSGE structure might produce more realistic numerical results but would complicate the analysis in a way that obscures the interaction between interest rates and local equity. As discussed in [Section VIII.A](#), complicating the analysis in this way would likely amplify many of our conclusions.

The starting point is a standard consumption-savings model with income shocks and borrowing constraints as in [Huggett \(1993\)](#). To this standard framework, we add housing and mortgages. Houses are subject to stochastic regional house price shocks, and agents can borrow against the value of their homes using FRMs that can be refinanced by paying a fixed cost. We account for equilibrium interactions between borrowers and lenders by assuming that mortgage payments are received by lenders in the economy who potentially adjust consumption when borrowers refinance.

### VI.A. Model Description

1. *Environment.* The economy is populated by a continuum of infinitely lived households, indexed by  $i$  and located in region  $j = 1, 2, \dots, J$ , and a representative lender.

2. *Idiosyncratic Earnings.* In each period  $t$ , a household's nominal earnings are given by  $y_t^{ij}$ , which follows a random walk with drift,

$$\log(y_t^{ij}) = \mu_y^j + \log(y_{t-1}^{ij}) + \varepsilon_t^{ij},$$

with region-specific income drift  $\mu_y^j$  and mean zero income shock  $\varepsilon_t^{ij}$ , which is i.i.d. over time but possibly correlated both across and within regions.

3. *Assets and Liabilities.* Households have access to a risk-free nominal asset  $a_t^{ij}$  paying nominal interest rate  $r_t$ , with a no-borrowing constraint  $a_t^{ij} \geq 0$ . They are endowed with one unit of housing with nominal price  $q_t^j$ , which can be used as collateral for mortgage borrowing. House prices follow a random walk with drift,

$$\log(q_t^j) = \mu_q^j + \log(q_{t-1}^j) + v_t^j,$$

where  $\mu_q^j$  is region-specific trend house price growth and  $v_t^j$  is a mean zero individual house price shock that is i.i.d. over time but is perfectly correlated within a region.

We assume that both earnings and house prices are random walks for two reasons. The first is computational: it allows us to reduce the state space, as we show in [Online Appendix A](#). The second is because it simplifies aggregation: households can be collected into regions and aggregated in a straightforward manner without adding additional state variables because aggregate, regional, and idiosyncratic household shocks enter symmetrically in the problem.

Since our empirical evidence focuses on refinancing for non-moving households, we assume for simplicity that agents cannot buy or sell houses and that mortgage debt is of infinite maturity. Nominal mortgage debt requires a constant mortgage payment  $r_{\tau_0}^m m_{\tau_0}^{ij}$  every period, which is determined at the moment of debt issuance  $\tau_0$ . However, households can refinance their mortgage at any time  $\tau > \tau_0$  by paying a fixed monetary cost  $F_{\tau}^{ij} q_{\tau}^j$ .<sup>27</sup> We assume that  $F_{\tau}^{ij}$  is an i.i.d. stochastic process that is uncorrelated with house prices or income in order to generate heterogeneity in refinancing decisions conditional on other household states and thus better fit the data, but our conclusions are similar if this randomness is eliminated.

When refinancing, households lock in the current nominal interest rate  $r_{\tau}^m$  and future mortgage payments  $r_{\tau}^m m_{\tau}^{ij}$ . Furthermore, we assume that when refinancing, households always borrow up to the maximum amount allowed by the loan-to-value requirement  $\gamma$ . This simplifies the household decision problem and computations in our benchmark model, but we show in

27. We assume the fixed cost is proportional to current house prices so that these costs remain relevant in the presence of house price growth and because this is necessary to make the household value function homogeneous in house prices.

Section VIII.C that relaxing this assumption has little effect on our conclusions. This implies that the new mortgage balance is  $m_t^{ij} = \gamma q_t^j$  and that cashed-out equity is  $m_t^{ij} - m_{\tau_0}^{ij}$ . These borrowing constraints capture the primary features of fixed-rate mortgages with options to refinance common in the United States. Finally, we assume nominal interest rates  $\{r_t, r_t^m\}$  follow an exogenous Markov process, which we discuss in the calibration.

4. *Household Problem.* For notational clarity, we drop agent and region indexes  $ij$  when describing the household problem. We start by describing how households' sequential budget constraints at time  $t$  depend on refinancing decisions and then formally state the household problem and value function.

In a period where the household does not refinance, the sequential budget constraint is

$$p_t c_t + a_{t+1} \leq a_t(1 + r_t) + y_t - \gamma r_{\tau_0}^m q_{\tau_0},$$

where  $c_t$  is period  $t$  real consumption and  $p_t$  is the price level. In a period where the household refinances, the sequential budget constraint is

$$p_t c_t + a_{t+1} \leq a_t(1 + r_t) + y_t - \gamma r_t^m q_t + \gamma(q_t - q_{\tau_0}) - F_t q_t,$$

To state the household problem recursively, we express all variables relative to house prices. In particular, define  $\tilde{x}_t = \frac{q_{\tau_0}}{q_t}$  as the inverse of accumulated equity and  $\{\tilde{a}_t, \tilde{y}_t, \tilde{p}_t\}$  as real assets, real earnings, and consumption good prices in terms of house prices. Furthermore, to bound the value function and ensure real variables have a well-defined stationary distribution, we exogenously bound  $\tilde{y}$  between  $[\underline{y}, \bar{y}]$ , and assume earnings and house prices grow on average at identical rates (i.e.,  $\mu_y = \mu_q$ ). Finally, as with nominal interest rates, we assume  $\tilde{p}_t$  follows an exogenous Markov process that is possibly correlated with local house prices and earnings but grows on average at rate  $\pi$ .

Then the value function of a household with assets  $\tilde{a}$ , earnings  $\tilde{y}$ , accumulated equity  $\tilde{x}$ , mortgage rate and balance  $\{r_0^m, \gamma \tilde{x}\}$ , and facing prices  $\tilde{p}$ , current nominal mortgage rate  $r^m$ , nominal

interest rate  $r$ , and fixed cost  $F$  can be written recursively as,

$$\begin{aligned}
 & V(\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, r^m, r, F, \tilde{p}) \\
 &= \max\{V^{noref^i}(\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, r^m, r, F, \tilde{p}), V^{ref^i}(\tilde{a}, \tilde{y}, \tilde{x}, r^m, r, F, \tilde{p})\} \\
 & V^{noref^i}(\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, r^m, r, F, \tilde{p}) \\
 &= \max_{\{\hat{a}', c\}} u(c) + \beta \mathbb{E}[V\left(\hat{a}' \frac{\tilde{x}'}{\tilde{x}}, \tilde{y}', \tilde{x}', r_0^m, r^{m'}, r', F', \tilde{p}'\right) | (\tilde{y}, \tilde{x}, r^m, r, F, \tilde{p})] \\
 & \quad s.t. \quad \tilde{p}c + \hat{a}' \leq \tilde{a}(1+r) + \tilde{y} - \gamma r_0^m \tilde{x} \\
 & \quad \hat{a}' \geq 0, c \geq 0 \\
 & \quad \log(\tilde{x}') = -\mu_q + \log(\tilde{x}) - \nu \\
 & \quad \log(\tilde{y}') = \mu_y - \mu_q + \log(\tilde{y}) + \varepsilon - \nu \\
 & V^{ref^i}(\tilde{a}, \tilde{y}, \tilde{x}, r^m, r, F, \tilde{p}) \\
 &= \max_{\{\hat{a}', c\}} u(c) + \beta \mathbb{E}[V\left(\hat{a}' \frac{\tilde{x}'}{\tilde{x}}, \tilde{y}', \frac{\tilde{x}'}{\tilde{x}}, r^m, r^{m'}, r', F', \tilde{p}'\right) | (\tilde{y}, \tilde{x}, r^m, r, F, \tilde{p})] \\
 & \quad s.t. \quad \tilde{p}c + \hat{a}' \leq \tilde{a}(1+r) + \tilde{y} - \gamma r^m + \gamma(1-\tilde{x}) - F \\
 & \quad \hat{a}' \geq 0, c \geq 0 \\
 & \quad \log(\tilde{x}') = -\mu_q + \log(\tilde{x}) - \nu \\
 & \quad \log(\tilde{y}') = \mu_y - \mu_q + \log(\tilde{y}) + \varepsilon - \nu.
 \end{aligned}$$

Inspecting this problem, we can see the household's incentives to refinance. When the current interest rate  $r^m$  is below the rate when the household last refinanced  $r_0^m$ , the household can secure a permanently lower mortgage payment, even if house prices are unchanged. When the current house price is above the price when the household last refinanced, the household can refinance to cash-out accumulated equity  $\frac{1}{\tilde{x}_t}$  even if rates have not changed, but then faces greater future mortgage payments. Furthermore, when  $\mu_q > 0$ , households accumulate equity, on average, when not refinancing. Once enough time has passed to acquire substantial equity, it is optimal to refinance and cash out this equity. This

logic is typical of fixed adjustment cost models, where inaction is optimal until the state changes enough to justify paying the fixed cost. These models are often stylized enough that the state-space is one-dimensional with optimal policies characterized by a single adjustment “threshold.” This is not true in our setup since we have a richer state-space, with a state (assets  $\tilde{a}_t$ ) evolving endogenously when not refinancing. Numerical solutions nevertheless yield refinancing decisions characterized by threshold equity levels, which depend on assets, income, fixed costs, and interest rates.

Finally, to characterize policy functions numerically, it is helpful to eliminate a state variable. By assuming that households’ period utility function is  $u(c_t) = \frac{c_t^{1-\sigma}}{1-\sigma}$  with  $\sigma \geq 1$  and that  $\tilde{p}$  is a random walk with a drift, we show in the [Online Appendix](#) that we can eliminate  $\tilde{p}$  as a state variable because the value function is homogeneous of degree  $\sigma - 1$  in  $\tilde{p}$ . We denote this transformed value function  $J(\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, r^m, r, F)$ . The [Online Appendix](#) also provides a detailed description of our computational procedure. In practice, because we wish to compute aggregate consumption as well as its cross-regional variance, we need  $\tilde{p}$  to have a well-defined stationary distribution. As such, we assume that consumption good prices are proportional to local house prices, implying that  $\tilde{p}$  grows at a constant rate  $\pi - \mu_q$  and  $\tilde{c}$  can be interpreted as real consumption.<sup>28</sup>

**5. Regions.** Because we take income and prices as exogenous and abstract from moving, a region  $j$  in this economy is simply a collection of households that experience common shocks to house prices and income. Importantly,  $r^m$  is not indexed by  $j$ , so there is a single common mortgage rate for all regions. As discussed above and shown in [Online Appendix](#) Figure A-6, there is almost no spatial variation in mortgage rates in the data. Thus, we make this assumption for empirical realism. However, as we discuss in [Section VI.B](#), this also helps in moving from the regional responses to QE we measure in the data to the aggregate counterfactuals in our model. In particular, because we take  $r^m$  as exogenous and consider policy experiments which alter this rate by fixed amounts,

28. While we make this assumption mainly for simplicity and convenience, [Stroebel and Vavra \(2018\)](#) show that local retail prices indeed respond strongly to changes in local house prices. As an alternative, we have also performed all our computations by exogenously bounding  $\tilde{p}$  and our quantitative results are almost identical.

we do not need to specify anything about regional credit supply.<sup>29</sup> Finally, borrowers within a region have idiosyncratic income and equity (due to idiosyncratic prior refinancing decisions) but face the same regional income and house price shock and aggregate mortgage rate. Given these exogenous idiosyncratic and regional state variables, regional borrower outcomes are just the sum of the optimal borrower decisions in a region and aggregate borrower outcomes are the sum over all regions.

*6. Mortgage Lenders.* The previous subsections fully characterize the regional and aggregate behavior of borrowers in the model, but they are insufficient to characterize the overall consumption implications of the refinancing channel. This is because any change in mortgage liabilities and payments by borrowers necessarily means a change in mortgage assets and income for lenders, which may in turn affect lenders' consumption. For example, when borrowers refinance after a decline in interest rates, the dividends accruing to lenders decrease, which should reduce their consumption (see [Greenwald 2016](#)).

As we discuss in [Section VI.B](#), these aggregate lender consumption offsets are an important reason regional and aggregate responses to rate declines may not vary in the same way with equity. Although our empirical results can measure relative responses to interest rate changes across regions with different equity, any aggregate equilibrium effects are differenced out and cannot be identified. By including lenders in our structural model, we are thus attempting to quantify aggregate equilibrium offsets that cannot be measured directly in the data.

Since we have no data on the regional distribution of lenders, we assume that there is a national representative U.S. lender. However, a large fraction of mortgage debt is ultimately held by foreign lenders, and we do not want to count changes in their consumption as offsets against the consumption of domestic borrowers. Thus, we assume that mortgage debt is paid into a mutual fund and that a share  $\theta$  of this fund is held by a representative U.S. lender while share  $1 - \theta$  is held by foreign lenders (e.g., Chinese investors). This means that the representative lender ultimately holds a fixed fraction  $\theta$  of outstanding mortgage debt. For simplicity, we assume the representative lender is a

29. Rate equalization across space suggests perfectly elastic credit supply, but the partial equilibrium nature of our borrower problem means we only care about  $r^m$  and not the allocation of credit that generates this interest rate.

permanent income consumer and receives certain dividend payments  $d$  from the mutual fund (a consequence of a law of large numbers for households). Given a law of motion for dividends  $d' = \tilde{G}(\cdot)$ , the lender's value function is:

$$V_R(a_R, d, r) = \max_{c_R, a'_R} u(c_R) + \beta_R V(a'_R, d', r')$$

$$s.t. \quad c_R + a'_R \leq a_R(1+r)e^{-\pi} + \theta d$$

$$c_R \geq 0.$$

Importantly, the law of motion will be determined in equilibrium as a function of the refinancing decisions of all borrowers and the exogenous mortgage rate.<sup>30</sup> This in turn makes lender consumption an equilibrium object.

Finally, it is important to note that we always take the mortgage rate  $r^m$  as exogenous, and our policy experiments will involve changes in this rate. Thus, we implicitly assume that the Fed can adjust credit supply by whatever amount is necessary to target a given  $r^m$ . However, we do not care directly about these balance sheet changes and instead care only about the resulting interest rate. This is analogous to New Keynesian models where the Fed controls the interest rate with a Taylor rule but where the open market operations necessary to achieve this rate are not specified because they are irrelevant for model outcomes of interest.<sup>31</sup>

*7. Recursive Equilibrium Definition.* A recursive equilibrium is an initial distribution  $S$  for  $\{\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, F\}$  across households  $i$  in regions  $j$ ; initial lender assets  $a_R^0$ ; a law of motion for  $d', r^m$ , and  $r$ ; value functions  $J(\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, r^m, r, F)$ ,  $V_R(a_R, d, r)$ ; and policy functions  $[\hat{a}', \tilde{c}, \tilde{x}, \mathbb{I}^{efi}](\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, r^m, r, F)$  and  $[a'_R, c_R](a_R, d)$  such that

- i The policy functions solve households' and lender's problems.
- ii For all realizations of  $\{\tilde{y}_t(i, j), \tilde{x}_t(i, j), F_t(i, j), r_t^m, r_t\}_{t=0}^\infty$  across households and regions  $(i, j)$ , the law of motion

30. Since mortgage rates are exogenous, this is straightforward because we can calculate the present value response of dividends to a decline in interest rates entirely from the borrower side and then separately calculate lender consumption responses.

31. We also make the technical assumption that consumption responses to exogenous changes in credit by the Fed are identical to responses to changes in private lending so that we do not need to specify the share of total mortgage assets held by the Fed.

for dividends  $G(S, r^m, r)$  implied by the policy functions is equal to the perceived law of motion by lenders  $\tilde{G}(\cdot)$  and satisfies

$$d_t = \int \left[ (1 - \mathbb{I}_t^{refi}(i, j)) \gamma r_{0,t}^m(i, j) \tilde{x}_t(i, j) + \mathbb{I}_t^{refi}(i, j) (\gamma r_t^m + F_t(i, j) - \gamma(1 - \tilde{x}_t(i, j))) \right] didj.$$

This equilibrium definition does not impose market clearing on the asset and consumption market because we take interest rates, goods and house prices, and income as exogenously determined. However, the model endogenizes the effective interest rate (or return) received by mortgage lenders and, as a result, the price of the aggregate portfolio of mortgages. We focus on endogenizing these objects because they are crucial for determining lender consumption offsets that have the potential to dampen the aggregate conclusions one would draw from our regional evidence. In contrast, endogenizing other additional prices and imposing additional market clearing would mostly introduce effects orthogonal to our main channel of interest, or more importantly would typically amplify our effects of interest. We discuss this in more detail in [Section VIII.A](#) and provide some quantitative illustration of this point. Thus, our equilibrium definition specifically focuses on endogenizing the first-order features that might undo our conclusions of interest. For simplicity and transparency we abstract from other effects that would complicate our model but would likely amplify results.

### VI.B. *Understanding Model Assumptions to Move from Regions to Aggregates*

We have now completed the description of our model, but before discussing calibration and results, it is useful to discuss the particular assumptions embedded in this model that allow us to infer aggregate implications from cross-regional empirical evidence. When we turn to model results, we discuss a variety of outcomes simultaneously, but some of these outcomes rely on stronger assumptions than others. It is useful to make these assumptions explicit. Doing so also motivates some of our additional robustness exercises surrounding the stronger of these assumptions.

Specifically, we focus on how the response of aggregate refinancing and consumption to changes in rates varies with the

distribution of housing equity. Getting from regional refinancing responses to aggregate refinancing responses requires two key assumptions: (i) Our policy experiment is an aggregate mortgage rate shock and rates are equal in all regions; and (ii) an individual borrower cares only about his total equity and not its decomposition into regional and aggregate-driven components when determining his demand for refinancing.<sup>32</sup>

As discussed already, the first assumption is directly supported in the data. Furthermore, the assumption that our policy experiment is an aggregate rate shock means that we only need to know how demand for refinancing by borrowers varies with equity and do not have to specify anything about credit supply.<sup>33</sup> The second assumption implies that this refinancing-demand response does not change as house price shocks become more or less aggregate.<sup>34</sup> It can also be restated as an assumption that the elasticity of mortgage demand to rate changes in a small open economy is the same as in a closed economy. This assumption seems reasonable given the empirical evidence that refinancing responses to QE varied with equity in the same way for states as for MSAs. Together, these two assumptions are sufficient to move from regional to aggregate refinancing responses.

However, moving from regional refinancing responses to aggregate consumption responses requires additional structure and assumptions. First, in contrast to aggregate refinancing responses, aggregate consumption responses will depend on lender behavior. We thus show results for a variety of assumptions about lender offsets (see [Section VIII](#)). Second, consumption behavior will depend on income and house prices, which we take as exogenous. However, we provide evidence in our robustness results that modeling additional equilibrium responses would likely amplify our conclusions. While the exact magnitude of time-varying aggregate effects differs somewhat across a variety of robustness specifications, the broad implications are very robust: as long as fewer households refinance in response to rate declines when they

32. That is, a borrower considering refinancing will look at his current mortgage balance and house value but does not care about how the value of the house decomposes into individual, regional, and aggregate components.

33. If we studied credit supply instead of rate shocks, we would need further assumptions on the regional and aggregate elasticity of credit supply to determine effects on mortgage rates.

34. Assumption ii follows from (but is weaker than) our assumption that income and house price movements are exogenous random walks.

have less equity, aggregate refinancing will vary across time. As long as aggregate refinancing leads to aggregate consumption responses, there will be time-varying effects of monetary policy on consumption through the refinancing channel.

Finally, it is worth highlighting several differences between our environment and prior literature that attempts to infer some aggregate policy effect from regional elasticities. For example, a large literature has explored what aggregate implications can be drawn about government spending multipliers using regional evidence. In the government spending literature, the first challenge with identifying aggregate multipliers from regional multipliers is that regional and aggregate changes in government spending may have different equilibrium effects on taxes. For this reason, the literature often discusses the “deficit-financed” multiplier, holding taxes constant, but this multiplier may still differ for regional and aggregate government spending changes because these may have different effects on monetary policy and interest rates. These concerns are largely absent in our context for several reasons. First, we are not comparing a regional shock to an aggregate shock—we are just looking at how the effects of an aggregate shock differ across space. Second, since our aggregate shock is a change in interest rates, we do not need to worry about interest rate determination and potential differential interest rate feedback. Instead, the most important reason one should not interpret the empirical regional effects we identify as aggregate effects in our context comes from equilibrium consumption effects from lenders, which is why we focus explicitly on modeling this feedback.

### VI.C. Calibration Strategy

The model is annual, and most parameters are standard. As is common in the risk-sharing literature, we set  $\sigma = 2$  to generate an intertemporal elasticity of substitution of 0.5. We assume a constant nominal risk-free rate  $r = 0.03$ , inflation rate of  $\pi = 0.02$ , and set  $\beta = 0.95$ . For simplicity, we set  $\beta_R = \frac{1}{1+r}e^\pi$  so that lenders perfectly smooth consumption. For our baseline results, we assume the nominal mortgage rate is constant at  $r^m = 0.06$  and then show the response to a one-time, unanticipated permanent decline to  $r^m = 0.05$ , which roughly matches 30-year fixed rates before and after QE1. This specification illustrates effects transparently in the simplest possible environment and facilitates

numerical calculations, since it eliminates  $r^m$  expectations from the value function. In Section VIII, we instead assume that  $r^m$  follows an AR process and show that this delivers very similar quantitative conclusions. We set  $\gamma = 0.8$ , so that new mortgages require 20% equity and  $\theta = 0.5$  to account for the substantial fraction of U.S. mortgage debt held abroad, either directly (about 20% in 2008 Flow of Funds data) or indirectly through ownership of other institutions (such as banks) that hold mortgage debt. We show robustness to this assumption in Section VIII.

Following Kaplan and Violante (2010), income shocks are normally distributed with standard deviation of 0.1 to match earnings changes in PSID data. This is the total standard deviation of household income, but some portion of income is common to households in a region. The standard deviation of this common component is set to 0.025, to match our regional data. As described already, trend income and house price growth are assumed identical. We calibrate house prices to match the annual growth rate and standard deviation of nominal MSA house price changes from 1990 to 2014 in CoreLogic data of 0.025 and 0.065. We assume that in the stochastic steady state, shocks to house prices and income are independent. This independence on average is assumed when households make their policy decisions, but one of the primary questions we explore in our model is how particular realizations of shocks affect the consequences of monetary policy. During the Great Recession, house prices fell substantially on average, but there were substantial differences across regions, which were highly correlated with income changes. Since our empirical evidence is drawn from this period, we calibrate the remaining parameters of the model to match the distribution of house prices and income in 2008 and the refinancing responses across regions following QE1. We call this calibration our baseline economy.

More specifically, to construct our baseline economy we initialize the model from the stochastic steady state, but in period  $t$  we hit the economy with the aggregate house price decline of 12.5% observed in 2008.<sup>35</sup> Households are also hit with an additional regional house price shock which can take the value  $-12.5\%$ ,  $0\%$ ,  $+12.5\%$  so that one-third of regions experience a

35. Note that this is just the one-year decline in house prices relevant for determining equity at the onset of QE1, not the peak-to-trough decline in aggregate house prices.

total house price decline of 25%, one-third experience a decline of 12.5% and one-third experience no decline. The 25% decline is picked to match the house price decline for the lowest housing equity quartile in our empirical analysis, whereas the 0% change matches that in the highest housing equity quartile. This means regions in our model can be mapped directly to those in our empirical analysis. Similarly, we calibrate regions so they differ by  $-2$  std. dev.,  $0$  and  $+2$  std. dev. of the regional income shock. If these income shocks were uncorrelated with house prices our simulated economy would have nine regions, representing the  $3 \times 3$  combinations of house price and income shocks. However, we instead assume regional house price and income shocks are perfectly correlated in our baseline model to match the very high correlation in the Great Recession. This means our baseline economy effectively has three regions: relatively high house price and income, middle house price and income, and low house price and income.

Finally, the fixed cost process is calibrated to match the regional responses to mortgage rate reductions under QE1. In particular, we assume that each household draws an i.i.d. fixed cost each period that can take on either a high or a low value and pick the levels of the high and low fixed costs and their relative probabilities to target a monthly refinancing rate just prior to QE1 of 0.0025, an increase in the refinancing rate of 0.0025 in the lowest house price region, an increase of 0.0075 in the middle house price region, and an increase of 0.011 in the highest house price region. This matches the simple elasticity in the data between house price growth and refinancing.

We calibrate to the 2008 period rather than the stochastic steady state for several reasons. First, this is the period for which we have strong empirical evidence on the distribution of house price changes, income, and refinancing responses from our QE1 event study. Second, our loan-level data start in 2005. It is unclear that any year over the housing boom-bust represents a “normal” steady-state period. Furthermore, by design, monetary stimulus is correlated with recessions and so any empirical evidence on the effects of interest rate reductions is going to come from periods with negative aggregate conditions. That is, any empirical measure of refinancing elasticities to interest rate reductions will always be primarily identified from recession periods. Therefore, we explicitly target this elasticity during such a period in the model. Finally, we focus on the elasticity of refinancing to interest rate reductions across regions rather than aggregate changes in




FIGURE IX

Refinance Decision Follows a Threshold Policy

refinancing because aggregate relationships may be contaminated by other confounding unmodeled aggregate shocks.

Although not targeted by our calibration, we document in the [Online Appendix](#) that the household-level distribution of equity in the 2008 calibration of the model is a good fit to its empirical counterpart. In the model and data there is substantial household heterogeneity in equity, with a nontrivial fraction of households more than 20% underwater. Although it would be desirable to also compare model and data relationships between home equity, financial assets, and consumption at either the household or regional level, unfortunately, the data necessary to make these comparisons does not exist. Nevertheless, we view the model fit in the [Online Appendix](#) as well as the fact that the model reproduces cross-regional refinancing patterns before and after QE1 as a reassuring check on its quantitative usefulness.

#### VI.D. Theoretical Results in the 2008 Baseline Economy

[Figure IX](#) shows the threshold property for refinancing decisions in a stationary environment with permanently high or low mortgage rates for a household with median income and assets, as well as in a nonstationary environment right after a permanent




FIGURE X

## Response to Interest Decline by Region

For the baseline 2008 calibration, the refinancing impulse response function (IRF) shows the change in the monthly fraction of households refinancing in response to a one percentage point reduction in mortgage rates. The consumption (C) IRF shows the change in log consumption in response to the same one percentage point reduction in mortgage rates.

mortgage rate decline.<sup>36</sup> The refinancing equity threshold is lower when mortgage rates are permanently low than when they are permanently high, leading to more frequent refinancing. More important, right after a mortgage rate decline, households refinance at even lower levels of equity. Intuitively, refinancing is more frequent in an economy with low mortgage rates because the cost of borrowing—future mortgage payments—is lower, while the benefit—equity cash-out net of fixed costs—is independent of mortgage rates.<sup>37</sup>

Figure X shows the impulse response of each region to a decline in mortgage rates from 0.06 to 0.05 in the baseline

36. Since households cannot sell housing, extractable equity is all equity above the fraction  $1 - \gamma$  required when refinancing.

37. [Online Appendix](#) Figure A.11 shows how the refinancing threshold changes with assets and earnings.




FIGURE XI

## Aggregate Stimulus versus Cross-regional Inequality in 2008 and 2001

Impulse response functions show the change in the monthly fraction of households refinancing, log aggregate consumption, and log consumption variance across regions in response to a one percentage point reduction in mortgage rates. See text for the description of the baseline economy calibrated to match November 2008 as well as the model specification for the 2001 recession.

economy, which matches economic conditions in 2008. The top panel shows the change in the fraction of loans refinancing at a monthly rate. By construction, this matches the changes in Figure III, since the model is calibrated to hit these numbers. Just as in the data, regions with high equity are more likely to refinance in response to the decline in rates. The bottom panel shows that real consumption also responds more in high-equity regions. Although we do not have broad consumption data at the regional level, this is consistent with empirical patterns for auto spending in Figure V.

We next compute aggregate consumption and the variance of log consumption across regions. The solid lines in Figure XI show responses to the decline in mortgage rates in our 2008 baseline economy and give our first important theoretical result: a reduction in interest rates increases aggregate consumption but also increases the variance of consumption across regions. This increase

in variance occurs because consumption increases most in regions with high house prices.<sup>38</sup> Since house prices and income are correlated in this economy, these regions already have the highest income and consumption before the interest rate declines. Thus, while monetary policy increases overall consumption, it does so mainly by stimulating consumption in locations that are already doing relatively well.

This trade-off between aggregate stimulus and inequality is strongly suggested by our empirical results showing a strong correlation between house prices, income, refinancing, and auto spending around QE. However, the model addresses the concern that (i) our empirical results measure only cross-regional effects on borrowers and not offsetting aggregate effects from lenders and (ii) we do not have comprehensive empirical measures of regional consumption. Despite these potential concerns, our model nevertheless implies that under economic conditions in 2008, rate declines moderately increased aggregate consumption, but these benefits flowed most strongly to regions doing relatively well.

In terms of quantitative magnitudes, our model implies that a one percentage point rate decline under economic conditions in 2008 leads to an increase in aggregate consumption of 0.41%. We show below that this response more than doubles to 0.92% under economic conditions in 2001. For an aggregate point of comparison, VAR-based estimates that do not allow for time-varying responses imply aggregate consumption responses on the order of 0.5–2%. The standard errors in such time-series estimates are large, but these numbers nevertheless suggest that the refinancing channel of monetary policy is an important part of the overall monetary transmission mechanism, especially when there is substantial housing equity in the economy.

What drives these aggregate effects, and why do declines in lender consumption not fully offset increases in consumption by borrowers? First, some mortgage debt is owned by foreign lenders. Second, borrowers consume a large fraction of extracted equity on impact while lenders smooth consumption by using the income they receive from future repayment of that borrowing, as shown in the [Online Appendix](#). To explore these effects more concretely,

38. Note that MPCs (Marginal Propensities to Consume) out of equity are mildly higher in the worst-off region relative to the best-off regions (0.52 versus 0.46) but that substantially greater equity extraction in the best-off region swamps this difference in MPCs.

we decompose the impulse response function (IRF) of consumption on impact arising from two different channels: (i) intertemporal effects from changing the timing of borrowing and lending and (ii) wealth transfers between lenders and borrowers arising from changes in the present value of monthly payments. The first channel represents pure cash-out effects taking the present value of payments as given, while the second channel arises from both changes in the mortgage rate (holding mortgage balances constant) and changes in the level of mortgage balances (holding rates constant).<sup>39</sup> Importantly, channel (1) is identically zero for lenders because they only care about the net present value of payments and not their timing. This means that this term is independent of equilibrium effects arising from lender offsets and so will not vary with the foreign share of lenders.

We find that in our baseline calibration, the total aggregate consumption response on impact arising from pure cash-out effects (i.e., the first channel) is 0.26%, relative to a total consumption response of 0.41%. Thus, in our baseline model, cash-out effects represent more than half of total aggregate effects. Remaining effects arise from a net increase in domestic consumption as monthly mortgage payments from borrowers to lenders decline. In our baseline model, these payment effects are fairly large, but this depends importantly on the fact that a substantial fraction of lenders are abroad and so have no effect on domestic consumption. In a closed economy version of the model in which all lenders are domestic, the cash-out effect is again 0.26%, but the total effect falls to 0.25%, so that 105% of the aggregate consumption response to interest rates on impact is driven by intertemporal cash-out effects.<sup>40</sup> Unsurprisingly, total aggregate consumption effects are even larger (0.57%) in a version of the model where all lenders are foreign so that there are no lender consumption offsets. Together these results show that equilibrium lender effects matter, but they do not completely undo the consumption response of borrowers because of the presence of cash-out refinancing.

39. Formally, we measure effect 2 by computing the net present value of payment changes for both borrowers and lenders and multiplying that times the domestic MPC out of wealth for borrowers and lenders. Effect 1 is then the difference between this payment effect and the total consumption response on impact.

40. The small effect of the payment channel is consistent with the logic in [Greenwald \(2016\)](#). The payment effect is slightly negative in the closed economy because the MPC out of permanent shocks for borrowers is slightly less than 1.

### VI.E. Counterfactual Analysis

That our model reproduces the behavior of the economy just before and after QE1 gives us confidence in using it for more ambitious counterfactual analysis. We now show that the theoretical effects of monetary policy are highly nonlinear with respect to the regional distribution of housing equity. This means that accounting for time variation in this distribution, which we documented in [Section V](#), is crucial for correctly predicting the aggregate and regional consequences of monetary policy.

1. *2008 versus 2001 Economic Conditions.* [Figure XI](#) compares the impulse response function of aggregate refinancing activity, aggregate consumption, and cross-regional consumption inequality to an interest rate shock in the 2008 baseline model to what would occur if regional house price patterns in 2008 had instead looked like those in 2001. Under the 2001 model distribution of shocks, house prices are constant for the lowest one-third of regions, rise by 5% for the middle third, rise by 10% for the highest third of regions, and regional house prices and income are uncorrelated.

As seen in [Figure XI](#), changing the equity distribution dramatically changes the consequences of monetary policy. In 2001, the same decline in interest rates raises aggregate consumption by 2.25 times as much as in 2008.<sup>41</sup> This means QE1 would have had much larger stimulative effects if enacted under the equity distribution in 2001 as opposed to 2008. There are two reasons for the larger consumption response. First, as shown in the top panel, the aggregate refinancing response to the rate decline is nearly twice as large in 2001 because fewer borrowers are underwater. Second, households that refinance have more equity to extract in 2001, which contributes to an additional consumption boost. Interestingly, as seen in the middle panel of the figure, inequality across regions falls mildly when rates fall in 2001 so that there is not always a trade-off between stimulus and cross-regional inequality.

To understand why the 2008 distribution of equity makes refinancing respond less to monetary policy than in 2001, it is useful to illustrate how equity interacts with refinancing

41. Specifically, consumption rises by 0.41% in the first year in 2008 versus 0.92% in 2001. The consumption of borrowers rises by 0.56% in 2008 and 1.15% in 2001, so lender offsets are similar in both years.




FIGURE XII

Distribution of Equity and Refinancing Probability: 2008 Calibration versus 2001

This figure shows the simulated distribution of equity and the fraction of households refinancing under two different equity distributions.

decisions. The three upward-sloping lines in Figure XII show the probability of refinancing as a function of extractable equity under different interest rate policies. These are analogous to the thresholds in Figure IX but averaging over the joint distribution of assets and income rather than conditioning on a particular value of these variables. When the interest rate is permanently 0.05 (the solid blue line; color version of this figure is available online) households are more willing to extract equity than when the interest rate is permanently 0.06 (the dashed red line) because borrowing is less costly. This means that the solid refinancing hazard line lies slightly above the dashed refinancing hazard line. The dotted yellow line is the most interesting since it shows the refinancing probability in the period when interest rates fall from 0.06 to 0.05. When rates fall, many more households refinance since refinancing delivers the benefit of extracting equity plus the benefit of locking in a lower rate. This means that the dotted line is substantially above the dashed line.

The vertical distance between the dotted and dashed lines shows the fraction of households who are induced to refinance by the interest rate decline at each level of extractable equity.

The aggregate increase in refinancing induced by the rate decline will then be the vertical difference between the dotted and dashed lines, weighted by the distribution of equity when the interest rate falls. This means that when the distribution of equity changes, the aggregate refinancing response to rate declines will change. The distribution of equity in our 2008 calibration is shown in green (square markers) and that in 2001 is shown in purple (round markers). In 2008, the distribution of equity shifts left and fans out relative to 2001. On net, this leaves much less mass of the equity distribution in the region where the difference between the dotted and dashed lines is large. That is, fewer refinancing decisions are triggered by rate declines in 2008 and so the refinancing impulse response to interest rates is reduced.

2. *Housing Equity Statistics and the Consequences of Monetary Policy.* The distribution of equity in 2008 in the model is different in three ways from 2001: it has a lower mean, greater cross-regional variance, and greater correlation between regional income and regional equity. To illustrate how each channel interacts with monetary policy, beginning from the 2008 baseline we show simple comparative statics in each moment.<sup>42</sup>

Figure XIII, Panel A shows the effect of changing the mean of the equity distribution at the time of a decline in interest rates. As the level of house prices rises, both inequality and aggregate consumption respond by more to the same decline in interest rates. Aggregate consumption responses increase with house prices, since more households are pushed into the part of the equity distribution where refinancing decisions respond to rate changes, and households also have more equity to consume conditional on refinancing. Cross-regional inequality responds more to rate declines when house prices rise because refinancing decisions and resulting consumption responses are highly convex in equity. In regions with negative equity, few households refinance and consumption responses are always near zero. This is true whether households are deeply underwater or only mildly underwater. In contrast, the consumption response to interest rates increases rapidly with equity as equity rises. This means that shifting the distribution of the equity to the right has no effect on

42. Moving from the solid blue line to the dashed red line in each figure roughly corresponds to changing from the 2008 value to the 2001 value of that moment while holding all others at the 2008 value.




FIGURE XIII

Effects of Changing Equity Distribution

Impulse response functions show the change in log aggregate consumption and in log consumption variance across regions in response to a one percentage point reduction in mortgage rates. The baseline economy includes a 12.5% aggregate house price decline. In Panel A, the “larger P decline” calibration features a 25% decline in house prices. The variance of equity and its correlation with income are fixed at the 2008 calibration across all simulations. In Panel B, the high variance calibration doubles the difference between high and low house price regions, while the low variance calibration halves it. All economies feature the same baseline decline in house prices and correlation with income. In the bottom panel, the baseline calibration has income and house prices positively correlated across regions. In the other two calibrations, they are uncorrelated or negatively correlated. All simulations feature the same baseline decline in house prices and variance across regions.

consumption responses for those on the left side of the distribution, while it increases them substantially for those on the right side of the distribution. Since initial levels of equity and income are positively correlated in our 2008 baseline, an increase in average equity increases the response of cross-regional inequality to rate declines.

Figure XIII, Panel B shows the effects of changing the variance of equity across regions. An increase in the variance of equity amplifies both the response of consumption inequality and aggregate consumption to rate declines. The intuition is almost identical to that for the effects of mean shifts and again follows immediately from Figure XII. Moving households with low equity to even lower equity has no effect on consumption responses to monetary policy, since these households do not refinance anyway. In contrast, additional equity amplifies the consumption response of those households on the right side of the distribution with substantial equity.

Finally Figure XIII, Panel C shows effects of changing the correlation between income and equity. If income and equity are uncorrelated, then interest rate declines have almost no effect on cross-regional inequality and when income and equity are negatively correlated, declines in interest rates substantially reduce cross-regional inequality. In contrast, the correlation between income and equity has almost no effect on aggregate consumption impulse responses. The intuition for inequality effects is straightforward. Consumption levels are higher in high-income than low-income regions. Consumption responses to interest rate changes are higher in high-equity than in low-equity locations. Thus, when income and equity are correlated, interest rate declines exacerbate the initial consumption inequality. If income and house prices are instead uncorrelated, as in the stochastic steady state or our 2001 calibration, then changes in consumption when interest rates fall are largely uncorrelated with initial levels of consumption. If instead they are negatively correlated, inequality is reduced.

The intuition for the lack of aggregate effects is slightly more subtle and reflects two offsetting forces. Overall, consumption growth is largest for regions with high house price growth and low income, since they have more equity and are also more liquidity constrained. However, low-income regions also have lower initial consumption levels than high-income regions. This means that the change in consumption levels for high-equity, high-income regions is similar to that of high-equity, low-income regions, so that

changing the proportion of such regions by altering the correlation between income and house prices has a negligible effect on aggregate consumption responses.

Of course, as shown in [Figure XII](#), the interaction between refinancing and the equity distribution is highly nonlinear, so the effects of changing any one moment of the equity distribution will always depend on the initial distribution of equity. For example, effects of a given aggregate house price shock on monetary policy will depend on the initial mean and variance of equity, since both features of the initial distribution will determine how the mean shift interacts with nonlinear refinancing decisions. The foregoing analysis shows the effects of particular changes under the 2008 initial distribution, but the policy function in [Figure XII](#) implies the equity distribution will matter much more generally.

An additional robustness analysis in the [Online Appendix](#) illustrates this more concretely by showing that shifts in the mean ( $\mu$ ) of the equity distribution have effects on monetary policy that depend on the standard deviation ( $\sigma$ ) of the distribution. In particular, we have just shown that the aggregate consumption response to rate cuts grows with mean equity:  $\frac{\partial IRF}{\partial \mu} > 0$ . In the [Online Appendix](#) we show that this positive relationship is diminishing with  $\sigma$ :  $\frac{\partial^2 IRF}{\partial \mu \partial \sigma} < 0$ . That is, the same increase in mean house prices has a smaller effect on the response of consumption to rate drops in a high  $\sigma$  environment. This is because when  $\sigma$  is large, more households are either deeply underwater or have so much equity that they will extract it even without a decrease in rates. A rightward shift in the equity distribution then has relatively modest effects, since it does not induce deeply underwater households to refinance and makes households with substantial equity even less sensitive to monetary policy. These results demonstrate that the effects of shocks to average equity for monetary policy cannot be determined without knowing the full equity distribution. A corollary of this result is that understanding the refinancing channel of monetary policy requires a full accounting of the distribution of equity and so cannot be analyzed in frameworks which abstract from heterogeneity.

## VII. INTERACTION WITH MORTGAGE MODIFICATION POLICIES

The analysis thus far argues that monetary policy in 2008 provided the least stimulus to regions which needed it most

and that this dampened its aggregate effects. We now show that various complementary mortgage modification programs which capture elements of policies implemented in the Great Recession can boost the effectiveness of monetary policy in such situations.


We explore two mortgage modification policies: debt forgiveness and relaxed refinancing requirements. We intentionally implement these policies in a stylized fashion to starkly illustrate their interactions with monetary policy, but the first policy captures elements of the mortgage write-downs available to some borrowers under HAMP, while the second is more similar to the HARP program.<sup>43</sup> We model debt forgiveness by assuming that a portion of mortgage debt for any household that is underwater in 2008 is forgiven. In particular, all households with an LTV greater than  $\gamma$  have their loans adjusted so that  $LTV = \gamma$ .<sup>44</sup> Importantly, this debt write-down is larger than typical debt forgiveness under HAMP. Again, we are not trying to provide a quantitative evaluation of HAMP and instead just want to illustrate interactions between debt forgiveness and monetary policy under a very simple policy experiment. Under the relaxed refinancing requirements policy, we allow underwater households to refinance rates without meeting the LTV requirement. To reflect the fact that these policies also explicitly eliminated appraisal and other fees associated with refinancing, we assume that underwater households can refinance without paying the fixed cost under both policies.

Figure XIV, Panel A shows the response to these modification programs, holding interest rates constant. That is, it shows the effects of the programs alone with no simultaneous

43. Existing research has shown that institutional features such as servicer participation and market power matter for the consequences of these policies as actually implemented (Agarwal et al. 2017a, b). Also, especially with modification programs, which in practice usually focus on delinquent borrowers, moral hazard is an important concern that we do not consider. We are not evaluating the specifics of program implementations in the Great Recession or the detailed institutional design of any such programs. We are instead interested in the broad ways in which such programs, independently implemented by the fiscal authority, might affect the consequences of monetary policy.

44. We account for the negative effect of this policy on lenders, although in reality, lenders would likely be compensated by the government, which in turn would raise taxes. But these taxes would likely be borne disproportionately by the richer lenders. Even with lump-sum taxes from all households, borrowers with forgiven debt would receive a net transfer.

(a): Response to Mortgage Modification w/ Constant  $r^m$ (b): Response to Mortgage Modification +  $r^m$  Decline



(c): Response to  $r^m$  Decline, Taking Mortgage Modification Programs as Given




FIGURE XIV

Mortgage Modification Effects

Panel A shows the effects of the debt reduction and relaxed refinancing requirement policies described in the text when interest rates are held fixed. Panel B shows the effects of simultaneously reducing rates and implementing the modification policies. Panel C shows the change in output and inequality from reducing interest rates and implementing mortgage modification relative to an economy that implements mortgage modification but has no decline in rates.

monetary policy change. The debt reduction program increases total consumption in the economy as it redistributes resources from unconstrained lenders to more constrained borrowers.<sup>45</sup> It also reduces cross-regional inequality, since debt forgiveness is available only to underwater households. In contrast, relaxing refinancing

45. These effects are tiny on impact but grow with time. This is consistent with conclusions in Ganong and Noel (2017) that debt forgiveness has little effect on consumption if, as in our experiment, households still have no equity after forgiveness.

requirements has no effect when interest rates are held constant because underwater households have no reason to refinance, even if it is costless, when rates are constant. Thus, this policy has no effect in the model unless accompanied by a reduction in mortgage rates.

Figure XIV, Panel B shows the response to simultaneously lowering rates and implementing mortgage modification. That is, it shows the combined effects of these policies. For comparison, we also show the baseline economy with a rate decline but no mortgage modification. Relative to the baseline, the combined policies lead to larger increases in spending and smaller increases in inequality.

Since impulse responses in Figure XIV, Panel B are computed relative to an economy without either mortgage modification or monetary policy, they tell us the combined effects of these policies. In contrast, Panel C isolates impacts of monetary policy from the direct effects of mortgage modification. In particular, we compute consumption statistics with rate declines and mortgage modification relative to an economy with mortgage modification but no rate decline. Clearly, the presence of either modification program increases the effectiveness of monetary policy and reduces its inequality effects. Interestingly, from the perspective of monetary policy, these two mortgage modification programs work nearly identically. Both policies increase the sensitivity of underwater households to changes in rates and so amplify the response of spending to interest rate declines. The fact that debt forgiveness has larger effects than relaxed refinancing requirements in Panel B arises because this policy has direct effects on the economy independently of rate changes, while the relaxed refinancing requirements policies work only through their interaction with interest rates. Because debt forgiveness has both direct effects as well as interaction effects with monetary policy, the combined effects are ultimately larger. However, implications for the efficacy of monetary policy are nearly identical.

Thus, even though the regional distribution of shocks in 2008 substantially hampered monetary policy transmission, there is at least some scope for mitigating these effects under such conditions. Policies that help underwater households refinance can interact importantly with interest rate changes to amplify effects of monetary policy and minimize their consequences for cross-regional inequality.

## VIII. ROBUSTNESS AND MODEL EXTENSIONS

In this section, we consider many model extensions and show that time variation in the consequences of monetary policy continues to hold. Although the quantitative magnitudes vary a bit across specifications, the qualitative conclusions are very robust since they are driven by two simple features of the economy: (i) underwater households cannot refinance without putting new cash into the house, which makes policy functions very nonlinear in equity, and (ii) the regional distribution of equity changes over time. Time-varying refinancing responses to rate changes arise immediately from the interaction of these two features. Because this nonlinearity is highly robust across models (and indeed in any reasonable model, underwater households should not be able to refinance and tap into home equity), it is unsurprising that our conclusions are equally robust. Our discussion is intentionally brief; additional details are provided in the [Online Appendix](#) for interested readers.

*VIII.A. General Equilibrium Effects*

Our baseline analysis allows for equilibrium offsets from the interaction between borrowers and lenders, but the size of these offsets depends on the domestic share of lenders. Our baseline assumes 50% of mortgage payments ultimately go to non-U.S. lenders, but measuring the foreign share of lenders is difficult since a large share of mortgage debt is held by commercial banks, which are owned in part by foreigners. As an additional robustness exercise, we explore two extreme assumptions for mortgage debt holdings. This also allows us to assess the importance of equilibrium lender forces for our results.<sup>46</sup> As the foreign share of lenders declines, equilibrium offsets grow in importance and aggregate consumption responds less to rate cuts. However, short-run effects remain positive even in the unrealistic case where all mortgage payments go to domestic households, so none of our conclusions about short-run stimulus-inequality trade-offs are altered. This is because, as discussed already, cash-out refinancing is an important part of stimulus effects. Since we assume lenders

46. Note that this is isomorphic to changing the MPC out of permanent income for lenders and so also provides robustness to changing the consumption behavior of lenders.

are equally distributed geographically, their behavior is irrelevant for cross-regional results.

Although we endogenize lender offsets, our model treats income and house prices as exogenous to simplify the analysis and provide more transparent intuition for our main mechanism. However, endogenizing income and house prices in a more fully fledged DSGE framework should amplify our conclusions. We find that refinancing activity and consumption responses to interest rates are stronger in well-off regions. If some portion of spending is on nontradable goods and if greater mortgage borrowing drives up house prices, then income and house prices will rise more in initially well-off locations, amplifying initial inequality. Similarly, endogenizing aggregate income and house prices will amplify aggregate time variation if greater aggregate spending generates greater aggregate income, as in New Keynesian models. In fact, in the representative agent model of [Greenwald \(2016\)](#), endogenizing house prices indeed amplifies the feedback from equity shocks to monetary stimulus.<sup>47</sup> To provide some quantitative evaluation of equilibrium income effects, we solve a simple extension of our model that partially accounts for this feedback. In particular, let  $\Delta c_t^j$  be the response of consumption in region  $j$  to the decline in  $r^m$  for  $t = 2001$  and  $t = 2008$  in our baseline model with exogenous income. Instead of assuming income is fixed when  $r^m$  declines, we assume that income in region  $j$  rises by  $\gamma \Delta c_t^j$  when  $r^m$  declines and that households take this income response into account when making their refinancing and consumption decisions. This model thus accounts for part of the equilibrium response of income to changes in demand under fixed prices. In particular, it accounts for the first round of the response of income to changes in demand but is not a full characterization of equilibrium income responses since it does not account for further multiplier effects beyond this first-round response. However, this allows us to provide some partial assessment of the role of equilibrium feedback without solving for the full equilibrium fixed point.

[Online Appendix](#) Figure A.15 shows results for this model, calibrating  $\gamma = 0.40$  to match a simple measure of the nontradable share of nonhousing personal consumption expenditures in

47. We thank Dan Greenwald for computing these results.

2008 and 2009.<sup>48</sup> This figure shows that, as anticipated, time variation in both cross-regional and aggregate effects are amplified by including endogenous income feedback but the basic qualitative patterns are unchanged.<sup>49</sup> Since the quantitative size of “second-round” consumption effects is an order of magnitude smaller than first-round effects, computing the more complicated full equilibrium income response would likely deliver very similar effects.

We also take aggregate inflation as exogenous. If inflation rises when interest rates fall, this introduces a nominal debt revaluation effect that transfers resources from lenders to borrowers. Such interactions are previously explored extensively in [Auclert \(2017\)](#).

Finally, we take  $r$  and  $r^m$  as given and do not impose liquid asset market clearing. However, when  $r^m$  falls, liquid savings rise mildly. If we imposed asset market clearing, this would lead to a small decline in  $r$  and increase in consumption through standard intertemporal-substitution channels. Furthermore, this asset response increases with the strength of the refinancing response to  $r^m$ . Thus, imposing asset market clearing would complicate the model but amplify our effects.

### VIII.B. Accounting for Additional Heterogeneity

1. *ARM Shares.* Our baseline analysis assumes that all mortgages have fixed rates. In reality, a substantial fraction of households have adjustable-rate mortgages (ARMs) whose rates reset even if households do not refinance. The presence of ARMs has some potential to change the refinancing channel of monetary policy. On the one hand, with ARMs, payments decrease when rates decline even if households do not refinance.

48. Using larger values of  $\gamma$  leaves the qualitative conclusions unchanged but, unsurprisingly, modestly amplifies the importance of equilibrium income feedback. We classify the following BEA spending categories as nontradable: food services and accommodations, health care, motor vehicle services, ground and water public transportation, recreation services, nursery, elementary and secondary education, commercial and vocational schools, professional and other services, personal care and clothing services, social services and religious activities, and household maintenance.

49. In the model with exogenous income, the  $r^m$  decline raises aggregate consumption (regional variance) by 0.4% (16.5%) in 2008 and 0.96% (−3.7%) in 2001. With partially endogenous income, the  $r^m$  decline raises aggregate consumption (regional variance) by 0.43% (17.7%) in 2008 and 1.26% (−4.3%) in 2001.

To the extent that borrowers have higher MPCs than lenders, this should amplify the spending response to monetary policy (e.g., Auclert 2017). On the other hand, the presence of ARMs reduces the interaction between cash-out decisions and interest rate declines because households do not need to accelerate equity extraction to take advantage of lower rates today. This makes cash-out-based spending less responsive to monetary policy.

Accounting for ARMs also potentially matters for cross-regional inequality, because ARM shares of outstanding loans in November 2008 were higher in MSAs with lower equity. We show these patterns in the [Online Appendix](#). ARM shares increased more during the boom years in areas with larger price increases, which subsequently experienced larger busts. Because ARMs were more prevalent in low-equity regions, it is possible more mortgages experienced rate declines in these regions despite our previous evidence that FRMs were less likely to be refinanced.

The importance of ARM offsets depends crucially on what fraction of ARM borrowers actually saw rate resets after QE1. There are many reasons not all ARM borrowers benefit from rate declines: (i) most ARMs are “hybrids” with initial fixed-rate periods of 3–10 years; (ii) ARMs typically have “rate floors,” which are often set at the initial rate of the loan; and (iii) the initial fixed-rate period often coincides with an interest-only (IO) period during which the borrower pays only interest and not principal. When the IO period ends, required payments jump up, which can more than offset simultaneous rate decreases. The [Online Appendix](#) shows the share of ARMs that experience significant rate reductions of 1 percentage point or more from November 2008 to June 2009 against  $E_{j,Nov2008}^{med}$ . Cross-MSA differences in rate resets are muted relative to differences in ARM shares. Overall, the variation in ARM resets with  $E_{j,Nov2008}^{med}$  is less than half that of FRM refinancing propensities so that declines in effective rates were still larger in high-equity MSAs after accounting for ARMs.

To explore the role of ARMs for our theoretical results, we solve a model in which some households borrow using FRMs while others use ARMs. ARMs in the model adjust every period to the current mortgage rate, and we calibrate regional ARM shares to

match the data.<sup>50</sup> In light of this discussion, this overstates the actual cross-regional variation in ARM resets after QE1. Thus, it is a conservative upper bound on the extent to which ARMs change our results. Even under this conservative calibration, ARMs have little effect on our conclusions. Low-equity regions have more ARM but fewer FRM rate resets. On net, the FRM effect dominates so that there are more rate reductions in high-equity regions. Moreover, low-equity regions have no cash-out activity because there is no equity to remove, while high-equity regions have significant cash-out and spending response to rate declines.<sup>51</sup>

We also separately decompose the role of ARM and FRM borrowers in determining aggregate time-series variation in spending responses to rate declines. Clearly, time variation is much larger for FRM borrowers than ARM borrowers, and aggregate spending patterns are much closer to those of FRM borrowers because they are a larger share of the economy. However, the spending response of ARM borrowers still declines by 20% in 2008 relative to 2001. It is also interesting to note that in 2001, FRM borrowers respond more to rate declines than ARM borrowers, in contrast to typical intuition that more flexible mortgages amplify responses to monetary policy. This is because when FRM borrowers actively refinance, they also extract equity and thus front-load their increase in spending, while passive rate resets under ARMs do not result in equity extraction.

*2. Strength of Cross-Regional Effects.* Our baseline model calibrates refinancing costs to match the raw correlation between refinancing and equity across regions in the data after QE1. As discussed earlier, the strength of this relationship depends on what additional covariates are included in regressions. To explore the robustness of our results to smaller responsiveness of local refinancing to housing equity, we solve a model with less regional heterogeneity in refinancing by doubling fixed costs, which roughly halves the cross-regional differences in refinancing after

50. We assume that the mortgage rate on ARMs and FRMs is identical and so abstract from yield-curve effects emphasized by Guren, Krishnamurthy, and McQuade (2018). However, due to the zero lower bound, long rates actually respond more than short rates to QE, so our assumption is relatively conservative.

51. Since this result is driven by variation in equity, it is consistent with results in Di Maggio et al. (2017) that after conditioning on equity, greater ARM shares are associated with larger spending responses to rate changes.

QE1. Clearly the exact magnitude of our effects is moderately reduced, but the qualitative patterns remain unchanged and time variation remains economically significant.

3. *Preceding Booms.* Does the boom-bust nature of the Great Recession where regions with the largest house price declines previously had the largest house price booms change our implications for cross-regional inequality? To assess this, we repeat our baseline exercise but in a model where the house price bust is preceded by a boom of equal magnitude. We find that our conclusions are unchanged in such an exercise.

### VIII.C. *Endogenous Cash-out*

In our baseline model, we abstract from the distinction between cash-out and non-cash-out refinancing by assuming households always extract all available equity when refinancing. We make this assumption largely for tractability, but find that it makes little difference for our conclusions. In particular, the [Online Appendix](#) shows that our results are very similar in a model where households can choose between a cash-out refi, modeled as before, and a pure rate refi, in which they lower their rate but do not cash out any equity. Allowing households to choose between cash-out and non-cash-out refi makes little difference because households in high-equity locations typically extract equity when refinancing anyway, and households in low-equity locations on average have little equity to extract, so the distinction between a cash-out and a rate refi is less relevant.

### VIII.D. *Interest Rate Process*

In our baseline, we assume mortgage rates are constant across time and show responses to one-time unanticipated declines in these rates. In response to QE1, mortgage rates declined and remained low for an extended period of time. This one-time shock results in the simplest environment and increases the computational tractability of the model, which allows some of the robustness exercises in this section. However, we also explored how our results change when  $r^m$  instead follows an AR process, with persistence of 0.89 and standard deviation of 0.0055 to match 30-year mortgage rates from 1990 to 2015. We find that our results are quantitatively similar under both

specifications. Given this, we use the simpler one-time shock as our baseline.

Our baseline model also assumes that monetary policy lowers the long-term mortgage rate  $r^m$  but not the short rate  $r$ . This describes the behavior of rates during QE1 because short-term rates were at the zero lower bound. However, monetary policy typically results in both rates falling. We find that our results are similar when we lower both  $r$  and  $r^m$  to maintain a constant spread. This means that our results apply to QE1 and to more conventional monetary policy since Gilchrist, Lopez-Salido, and Zakrajsek (2015, p. 77) argue that “the efficacy of unconventional policy in lowering real borrowing costs is comparable to that of conventional policy” throughout the yield curve. Because both conventional and unconventional monetary policy move mortgage rates, our results thus apply to monetary policy in general.<sup>52</sup> However, our results are quite different when we instead lower only  $r$  and not  $r^m$ . This experiment shows that the time-varying effects of monetary policy that we emphasize in this article work through the refinancing channel since the standard intertemporal channel arising from pure changes in short rates is both small and invariant to the distribution of equity.

### VIII.E. Income Process

The solution to the equity extraction problem balances transaction costs against the desire to extract housing equity. Because our baseline model includes only permanent income shocks, desired equity extraction is largely determined by past and current house price shocks and interest rate behavior rather than by a desire to smooth transitory income shocks. Introducing persistent but not permanent income shocks would substantially complicate the model solution, but it is straightforward to introduce completely transitory income shocks and thus a role for equity

52. Using the high-frequency monetary policy shocks from Gertler and Karadi (2015), we have explored whether the pass-through of short-term monetary policy shocks to mortgage rates varies with house price growth in the economy. Running a regression of monthly changes in the 30-year FRM rate on the Fed funds rate shocks interacted with annual national house price growth, we find strong pass-through of the federal funds rate to mortgage rates but no interaction with house price growth. This suggests that any time variation in the transmission of short to long rates that might exist in the data is orthogonal to time variation in the refinancing channel of monetary policy arising from movements in the distribution of equity.

extraction in smoothing income shocks. Doing so yields results that are very similar to the baseline model.<sup>53</sup> Furthermore, our baseline analysis assumes that regional income and house price shocks are uncorrelated. Since one of our points is that the correlation between regional income and house prices changes across time, the correct correlation to feed into the model is not obvious. Nevertheless, we find that our baseline findings are relatively conservative since results are amplified if we instead assume that regional income and house price shocks are perfectly correlated.

#### *VIII.F. Amortization and Life Cycle Effects*

Our model features interest-only mortgages, and so households do not accumulate equity through amortization. This means that our baseline calibration may understate the speed of equity accumulation in the data. Since households cannot buy or sell housing in our baseline model, faster house price growth is similar to including amortization, and we find that our conclusions are amplified if we increase house price growth. Thus, our baseline is again relatively conservative. Furthermore, life cycle effects mean that households tend to accumulate equity as they age. Life cycle effects can potentially have interesting interactions with the refinancing channel of monetary policy, as explored thoroughly in [Wong \(2016\)](#). As Wong emphasizes, these effects may change over time with population aging, but this is due to long-run secular trends and thus they are unlikely to drive the variation in effects of monetary policy at business cycle frequencies, which are the focus of our analysis. We thus abstract from life cycle effects since they would substantially complicate our analysis by introducing another state variable.<sup>54</sup>

#### *VIII.G. Housing Adjustment and Default*

We do not allow households to buy/sell housing or default on mortgages. Allowing households to move to extract equity would complicate the setup but would produce similar nonlinear interactions between equity and consumption. Introducing a construction sector and endogenous housing should also amplify

53. The standard deviation of these temporary shocks is set to 0.05 to match various estimates from earnings data.

54. Note also that our empirical results explicitly control for cross-regional variation in demographics.

our results. When households have more equity, there is more scope to purchase larger houses and increased housing demand will (i) drive up house prices and amplify initial equity differences and (ii) drive up construction, amplifying initial income differences.

Introducing an option to default and move to rental housing should similarly amplify cross-regional effects, especially in an environment with endogenous house prices. Only underwater households face default, risk. When rates fall, mildly underwater households may put cash into their homes to refinance, lower payments, and avoid default, but this is infeasible for deeply underwater households. As foreclosures have negative spillovers to local house prices, the places initially hit by large house price declines may enter house-price-foreclosure spirals. Because underwater homeowners in these locations have little ability to refinance into lower payments, rate declines will have little effect on default in the hardest hit locations and, thus, limited ability to arrest such foreclosure spirals.<sup>55</sup>

## IX. CONCLUSIONS

The Great Recession led to a prolonged period of monetary stimulus throughout much of the developed world. These policies are typically studied through the lens of representative agent New Keynesian models, which emphasize the importance of intertemporal substitution. In this article, we explore a complementary channel of monetary transmission through collateralized lending and show that understanding this channel requires moving beyond a representative borrower. Nonlinear interactions between collateral constraints, refinancing, and spending mean that the distribution of housing equity plays a crucial role in the economy's response to interest rate declines.

Using an equilibrium, heterogeneous household model of mortgage borrowing, we argue that the cross-regional distribution of housing equity during the Great Recession hampered the ability of monetary policy to stimulate aggregate spending through the

55. Of course, the welfare consequences of default must also account for the fact that homeowners may get some benefit from living in their homes during lengthy foreclosure processes and could get some benefit in certain situations from strategic default. However, we make no claims on the welfare consequences of default and merely argue that it would amplify the effects of cross-regional equity on monetary policy that are the focus of our analysis.

refinancing channel. Furthermore, large variation in house price growth that was strongly correlated with local economic activity meant that monetary stimulus largely flowed to the locations that needed it least. These theoretical conclusions rest on the distribution of equity, which is assumed away in typical representative agent analyses. Under alternative distributions of housing equity, such as that observed in 2001, aggregate monetary stimulus is much more powerful and can potentially moderate regional business cycles.

We provide evidence of these collateral effects using novel household-level data on mortgage debt and refinancing. We show that after QE1, there was an aggregate increase in refinancing, but there was little response in the hardest hit regions, where many households were underwater. The empirical distribution of house price growth was quite different during the 2001 recession: aggregate house price growth was positive throughout the recession, and regional house price growth was uncorrelated with local unemployment. Consistent with our theoretical predictions, there was much more refinancing activity during the 2001 easing cycle than during the Great Recession, and refinancing was actually more common in regions with high unemployment. Thus, the data confirm that variation over time in the collateral distribution is key for understanding the time-varying consequences of monetary policy.

Our data come from the U.S. mortgage market, so our analysis focuses on regional house price shocks because they are the dominant source of shocks to home equity. Changes in the distribution of other types of collateral will generate many of the same implications for monetary policy, but the relevant sources of shocks and heterogeneity may differ. For example, sectoral shocks may play an important role in influencing the distribution of collateral across firms and influence the response of investment to monetary policy through similar mechanisms. Variation across time in economic activity and its correlation with housing equity and other forms of collateral is also not unique to the United States. Europe has experienced persistent cross-country differences in economic growth that are highly correlated with house price movements. While the prominence of FRMs and other institutional features of mortgage contracts differs between the United States and Europe and across countries within Europe, [Section I](#) shows that our conclusions are not particularly sensitive to variation in fixed-rate shares. We leave a more thorough analysis of the effects of

the collateral distribution in these alternative contexts to future work, but our analysis suggests that central banks are likely to face trade-offs that vary importantly with the distribution of collateral. Since this distribution varies over time, tracking its evolution is crucial for accurately assessing the effects of monetary policy (see Fuster, Guttman-Kenney, and Haughwout 2018 for an effort along these lines).

MASSACHUSETTS INSTITUTE OF TECHNOLOGY AND NATIONAL BUREAU  
OF ECONOMIC RESEARCH  
SWISS NATIONAL BANK  
UNIVERSITY OF CHICAGO BOOTH SCHOOL OF BUSINESS AND NATIONAL  
BUREAU OF ECONOMIC RESEARCH  
UNIVERSITY OF CHICAGO BOOTH SCHOOL OF BUSINESS AND NATIONAL  
BUREAU OF ECONOMIC RESEARCH

#### SUPPLEMENTARY MATERIAL

An Online Appendix for this article can be found at *The Quarterly Journal of Economics* online. Code replicating tables and figures in this article can be found in Beraja et al. (2018), in the Harvard Dataverse, doi:10.7910/DVN/GETNJK.

#### REFERENCES

- Abel, Joshua, and Andreas Fuster, "How Do Mortgage Refinances Affect Debt, Default, and Spending? Evidence from HARP," *Staff Report 841*, Federal Reserve Bank of New York, 2018.
- Agarwal, Sumit, Gene Amromin, Itzhak Ben-David, Souphala Chomsisengphet, Tomasz Piskorski, and Amit Seru, "Policy Intervention in Debt Renegotiation: Evidence from the Home Affordable Modification Program," *Journal of Political Economy*, 125 (2017a), 654–712
- Agarwal, Sumit, Gene Amromin, Souphala Chomsisengphet, Tim Landvoigt, Tomasz Piskorski, Amit Seru, and Vincent Yao, "Mortgage Refinancing, Consumer Spending, and Competition: Evidence From the Home Affordable Refinance Program," NBER Working Paper No. 21512, 2017b.
- Alpanda, Sami, and Sarah Zubairy, "Household Debt Overhang and Transmission of Monetary Policy," *Journal of Money, Credit and Banking*, forthcoming (2018).
- Arrow, Kenneth J., Theodore Harris, and Jacob Marschak, "Optimal Inventory Policy," *Econometrica*, 19 (1951), 250–272.
- Auclert, Adrien, "Monetary Policy and the Redistribution Channel," NBER Working Paper No. 23451, 2017.
- Avery, Robert B., Neil Bhutta, Kenneth P. Brevoort, and Glenn B. Canner, "The Mortgage Market in 2010: Highlights from the Data Reported under the Home Mortgage Disclosure Act," *Federal Reserve Bulletin*, 97 (2011), 1–60.
- Barro, Robert, "A Theory of Monopolistic Price Adjustment," *Review of Economic Studies*, 39 (1972), 17–26.

- Beraja, Martin, Andreas Fuster, Erik Hurst, and Joseph Vavra, "Replication Data for: 'Regional Heterogeneity and the Refinancing Channel of Monetary Policy'" (2018), Harvard Dataverse, doi:10.7910/DVN/GETNJK.
- Beraja, Martin, Erik Hurst, and Juan Ospina, "The Aggregate Implications of Regional Business Cycles," NBER Working Paper No. 21956, 2016.
- Berger, David, Veronica Guerrieri, Guido Lorenzoni, and Joseph Vavra, "House Prices and Consumer Spending," *Review of Economic Studies*, 85 (2018), 1502–1542.
- Berger, David, and Joseph Vavra, "Consumption Dynamics during Recessions," *Econometrica*, 83 (2015), 101–154.
- Bernanke, Ben S., Mark Gertler, and Simon Gilchrist, "The Financial Accelerator in a Quantitative Business Cycle Framework," in *Handbook of Macroeconomics*, vol. 1 (Amsterdam: Elsevier, 1999), 1341–1393.
- Bhutta, Neil, and Benjamin J. Keys, "Interest Rates and Equity Extraction during the Housing Boom," *American Economic Review*, 106 (2016), 1742–1774.
- Brady, Peter J., Glenn B. Canner, and Dean M. Maki, "The Effects of Recent Mortgage Refinancing," *Federal Reserve Bulletin*, 86 (2000), 441–450.
- Caballero, Ricardo, and Eduardo Engel, "Explaining Investment Dynamics in U.S. Manufacturing: A Generalized (S,s) Approach," *Econometrica*, 67 (1999), 783–826.
- Canner, Glenn, Karen Dynan, and Wayne Passmore, "Mortgage Refinancing in 2001 and Early 2002," *Federal Reserve Bulletin*, 88 (2002), 469–481.
- Caplin, Andrew, Charles Freeman, and Joseph Tracy, "Collateral Damage: Refinancing Constraints and Regional Recessions," *Journal of Money, Credit and Banking*, 29 (1997), 496–516.
- Charles, Kerwin Kofi, Erik Hurst, and Matthew J. Notowidigdo, "Manufacturing Decline, Housing Booms, and Non-Employment," NBER Working Paper No. 18949, 2013.
- Chen, Hui, Michael Michaux, and Nikolai Roussanov, "Houses as ATMs? Mortgage Refinancing and Macroeconomic Uncertainty," NBER Working Paper No. 19421, 2013.
- Di Maggio, Marco, Amir Kermani, Benjamin J. Keys, Thomas Piskorski, Rodney Ramcharan, Amit Seru, and Vincent Yao, "Interest Rate Pass-Through: Mortgage Rates, Household Consumption, and Voluntary Deleveraging," *American Economic Review*, 107 (2017), 3550–3588.
- Di Maggio, Marco, Amir Kermani, and Christopher Palmer, "How Quantitative Easing Works: Evidence on the Refinancing Channel," NBER Working Paper No. 22638, 2016.
- Frame, W. Scott, Andreas Fuster, Joseph Tracy, and James Vickery, "The Rescue of Fannie Mae and Freddie Mac," *Journal of Economic Perspectives*, 29 (2015), 25–52.
- Fratantoni, Michael, and Scott Schuh, "Monetary Policy, Housing, and Heterogeneous Regional Markets," *Journal of Money, Credit and Banking*, 35 (2003), 557–589.
- Fuster, Andreas, Benedict Guttman-Kenney, and Andrew Haughwout, "Tracking and Stress-Testing U.S. Household Leverage," *Federal Reserve Bank of New York Economic Policy Review*, 24 (2018), 35–63.
- Fuster, Andreas, Stephanie H. Lo, and Paul S. Willen, "The Time-Varying Price of Financial Intermediation in the Mortgage Market," *Staff Report 805*, Federal Reserve Bank of New York, 2017.
- Fuster, Andreas, and Paul S. Willen, "\$1.25 Trillion Is Still Real Money: Some Facts about the Effects of the Federal Reserve's Mortgage Market Investments," Public Policy Discussion Paper 10-4, Federal Reserve Bank of Boston, 2010.
- Ganong, Peter, and Pascal Noel, "The Effect of Debt on Default and Consumption: Evidence from Housing Policy in the Great Recession," Working Paper, Harvard University, 2017.

- Garriga, Carlos, Finn E. Kydland, and Roman Sustek, "Mortgages and Monetary Policy," *Review of Financial Studies*, 30 (2017), 3337–3375.
- Gertler, Mark, and Peter Karadi, "Monetary Policy Surprises, Credit Costs, and Economic Activity," *American Economic Journal: Macroeconomics*, 7 (2015), 44–76.
- Gilchrist, Simon, David Lopez-Salido, and Egon Zakrajsek, "Monetary Policy and Real Borrowing Costs at the Zero Lower Bound," *American Economic Journal: Macroeconomics*, 7 (2015), 77–109.
- Greenwald, Daniel L., "The Mortgage Credit Channel of Macroeconomic Transmission," Working Paper, MIT Sloan (2016).
- Guren, Adam, Arvind Krishnamurthy, and Timothy McQuade, "Mortgage Design in an Equilibrium Model of the Housing Market," NBER Working Paper No. 24446, 2018.
- Hanson, Samuel G., David O. Lucca, and Jonathan H. Wright, "Interest Rate Conundrums in the Twenty-First Century," *Staff Report 810*, Federal Reserve Bank of New York, 2017.
- Hedlund, Aaron, Fatih Karahan, Kurt Mitman, and Serdar Ozkan, "Monetary Policy, Heterogeneity, and the Housing Channel," IIES Working Paper, 2017.
- Huggett, Mark, "The Risk-Free Rate in Heterogeneous-Agent Incomplete-Insurance Economies," *Journal of Economic Dynamics and Control*, 17 (1993), 953–969.
- Hurst, Erik, Benjamin J. Keys, Amit Seru, and Joseph S. Vavra, "Regional Redistribution through the US Mortgage Market," *American Economic Review*, 106 (2016), 2982–3028.
- Hurst, Erik, and Frank Stafford, "Home Is Where the Equity Is: Mortgage Refinancing and Household Consumption," *Journal of Money, Credit, and Banking*, 36 (2004), 985–1014.
- Iacoviello, Matteo, "House Prices, Borrowing Constraints, and Monetary Policy in the Business Cycle," *American Economic Review*, 95 (2005), 739–764.
- Kaplan, Greg, and Giovanni L. Violante, "How Much Consumption Insurance beyond Self-Insurance?," *American Economic Journal: Macroeconomics*, 2 (2010), 53–87.
- Mian, Atif, Kamalesh Rao, and Amir Sufi, "Household Balance Sheets, Consumption, and the Economic Slump," *Quarterly Journal of Economics*, 128 (2013), 1687–1726.
- Mian, Atif, and Amir Sufi, "What Explains the 2007–2009 Drop in Employment?," *Econometrica*, 82 (2014), 2197–2223.
- Rubio, Margarita, "Fixed- and Variable-Rate Mortgages, Business Cycles, and Monetary Policy," *Journal of Money, Credit and Banking*, 43 (2011), 657–688.
- Sheshinski, Eytan, and Yoram Weiss, "Inflation and Costs of Price Adjustment," *Review of Economic Studies*, 44 (1977), 287–303.
- Stroebel, Johannes, and Joseph Vavra, "House Prices, Local Demand, and Retail Prices," *Journal of Political Economy*, forthcoming (2018).
- Vavra, Joseph, "Inflation Dynamics and Time-Varying Volatility: New Evidence and an Ss Interpretation," *Quarterly Journal of Economics*, 129 (2014), 215–258.
- Winberry, Thomas, "Lumpy Investment, Business Cycles and Stimulus Policy," Working Paper, University of Chicago, 2016.
- Wong, Arlene, "Population Aging and the Transmission of Monetary Policy to Consumption," Working Paper, Northwestern University, 2016.

Online Appendix for  
Regional Heterogeneity and the Refinancing Channel of  
Monetary Policy

Martin Beraja, Andreas Fuster, Erik Hurst and Joseph Vavra

August 18, 2018

## A.1 MSA GROUPS USED IN FIGURES III, IV, AND V

Note: For large MSAs that are subdivided into Metropolitan Divisions, we use the latter (throughout the paper).

MSAs in the quartile with lowest  $E^{med}$  in November 2008:

Akron, OH; Anderson, IN; Bakersfield, CA; Bangor, ME; Battle Creek, MI; Bay City, MI; Bradenton-Sarasota-Venice, FL; Canton-Massillon, OH; Cape Coral-Fort Myers, FL; Carson City, NV; Cleveland-Elyria-Mentor, OH; Dalton, GA; Danville, IL; Dayton, OH; Deltona-Daytona Beach-Ormond Beach, FL; Detroit-Livonia-Dearborn, MI; El Centro, CA; Elizabethtown, KY; Elkhart-Goshen, IN; Fairbanks, AK; Flint, MI; Fort Lauderdale-Pompano Beach-Deerfield Beach, FL; Fort Walton Beach-Crestview-Destin, FL; Fort Wayne, IN; Fresno, CA; Grand Rapids-Wyoming, MI; Greeley, CO; Hagerstown-Martinsburg, MD-WV; Hanford-Corcoran, CA; Holland-Grand Haven, MI; Indianapolis-Carmel, IN; Jackson, MI; Jacksonville, FL; Kalamazoo-Portage, MI; Kankakee-Bradley, IL; Lake Havasu City-Kingman, AZ; Lakeland-Winter Haven, FL; Lansing-East Lansing, MI; Las Vegas-Paradise, NV; Madera-Chowchilla, CA; Mansfield, OH; Memphis, TN-MS-AR; Merced, CA; Miami-Miami Beach-Kendall, FL; Modesto, CA; Monroe, MI; Muskegon-Norton Shores, MI; Napa, CA; Naples-Marco Island, FL; Niles-Benton Harbor, MI; Oakland-Fremont-Hayward, CA; Ocala, FL; Orlando-Kissimmee, FL; Oxnard-Thousand Oaks-Ventura, CA; Palm Bay-Melbourne-Titusville, FL; Palm Coast, FL; Panama City-Lynn Haven-Panama City Beach, FL; Pensacola-Ferry Pass-Brent, FL; Phoenix-Mesa-Scottsdale, AZ; Port St. Lucie, FL; Providence-New Bedford-Fall River, RI-MA; Punta Gorda, FL; Redding, CA; Reno-Sparks, NV; Riverside-San Bernardino-Ontario, CA; Sacramento-Arden-Arcade-Roseville, CA; Saginaw-Saginaw Township North, MI; Salinas, CA; San Diego-Carlsbad-San Marcos, CA; Santa Rosa-Petaluma, CA; Sebastian-Vero Beach, FL; Springfield, OH; St. George, UT; Stockton, CA; Sumter, SC; Tampa-St. Petersburg-Clearwater, FL; Terre Haute, IN; Toledo, OH; Vallejo-Fairfield, CA; Visalia-Porterville, CA; Warren-Troy-Farmington Hills, MI; Weirton-Steubenville, WV-OH; West Palm Beach-Boca Raton-Boynton Beach, FL; Wheeling, WV-OH; Winchester, VA-WV; Worcester, MA; Youngstown-Warren-Boardman, OH-PA; Yuba City, CA; Yuma, AZ.

MSAs in the quartile with highest  $E^{med}$  in November 2008:

Albany-Schenectady-Troy, NY; Alexandria, LA; Anderson, SC; Asheville, NC; Athens-Clarke County, GA; Austin-Round Rock, TX; Baltimore-Towson, MD; Barnstable Town, MA; Baton Rouge, LA; Beaumont-Port Arthur, TX; Bellingham, WA; Bethesda-Frederick-Rockville, MD; Billings, MT; Binghamton, NY; Bismarck, ND; Blacksburg-Christiansburg-Radford, VA; Boulder, CO; Bridgeport-Stamford-Norwalk, CT; Buffalo-Niagara Falls, NY; Burlington-South Burlington, VT; Cambridge-Newton-Framingham, MA; Cedar Rapids, IA; Charleston, WV; Charlottesville, VA; Cleveland, TN; College Station-Bryan, TX; Corvallis, OR; Cumberland, MD-WV; Dubuque, IA; Duluth, MN-WI; Durham-Chapel Hill, NC; Edison-New Brunswick, NJ; Elmira, NY; Eugene-Springfield, OR; Fargo, ND-MN; Florence, SC; Fort Smith, AR-OK; Glens Falls, NY; Grand Forks, ND-MN; Grand Junction, CO; Great Falls, MT; Greenville-Mauldin-Easley, SC; Harrisburg-Carlisle, PA; Harrisonburg, VA; Hartford-West Hartford-East Hartford, CT; Honolulu, HI; Hot Springs, AR; Houma-Bayou Cane-Thibodaux, LA; Huntsville, AL; Iowa City, IA; Johnson City, TN; Kingsport-Bristol-Bristol, TN-VA; Lafayette, LA; Lake Charles, LA; Lancaster, PA; Lawrence, KS; Lebanon, PA; Longview, WA; Lynchburg, VA; Midland, TX; Missoula, MT; Mobile, AL; Mount Vernon-Anacortes, WA; Nassau-Suffolk, NY; New Orleans-Metairie-Kenner, LA; New York-White Plains-Wayne, NY-NJ; Ocean City, NJ; Philadelphia, PA; Pittsburgh, PA; Pittsfield, MA; Portland-Vancouver-Beaverton, OR-WA; Raleigh-Cary, NC; Reading, PA; Roanoke, VA; Salem, OR; San Angelo, TX; San Francisco-San Mateo-Redwood City, CA; San Jose-Sunnyvale-Santa Clara, CA; Seattle-Bellevue-Everett, WA; Sioux City, IA-NE-SD; Sioux Falls, SD; Spokane, WA; State College, PA; Trenton-Ewing, NJ; Tulsa, OK; Victoria, TX; Wenatchee-East Wenatchee, WA; Williamsport, PA; Wilmington, NC; Yakima, WA; York-Hanover, PA.

## A.2 ADDITIONAL DATA DESCRIPTION

### A.2.1 CRISM

We start with a 50% sample of all McDash (also known as LPS) mortgages linked to Equifax credit records that were outstanding for at least one month between January 2007 and December 2010. The CRISM data set provides the linked Equifax credit records for each McDash mortgage for the lifetime of the loan, including an additional 6 months before origination and after termination. This link is done directly by Equifax. Credit records provide a consumer's total outstanding debt amounts in different categories (first-lien mortgages, second-lien mortgages, home equity lines of credit [HELOCs], auto loans, etc.). Additionally, in any month, Equifax provides the origination date, amount, and remaining principal balance of the two largest (in balance terms) first mortgages, closed-end seconds, and HELOCs outstanding for a given consumer.

We convert these records into a loan-level panel with each loan's type, origination month, origination amount, termination month, and remaining principal balance for all months that the loan is outstanding. We restrict our sample to those consumers who start our sample with two or fewer loans in each category and never have more than three of any of these types of loans outstanding.<sup>1</sup> This amounts to about 96% of the population of Equifax borrower IDs, and these IDs cover about 90% of the loans in McDash. In creating this loan-level data set, we assume that the month in which the loan stops appearing in Equifax is the month that it was terminated.

The variables that McDash provides are already in the form of a loan-level panel and include: origination date, origination amount, remaining principal balance, termination date, termination type, lien type, interest type, property zip code, and purpose type. We match these to our Equifax panel. We consider an Equifax loan/McDash loan pairing a match if the origination date of the Equifax loan is within 1 month and the origination amount is within \$10,000 of the McDash loan. If more than one loan is matched, we use the origination amount, date, termination date, zip code, and termination balance as tiebreakers. We are able to match more than 93% of McDash loans using these restrictions, with more than 80% matching the origination information perfectly (up to \$1 in balances due to rounding).

We use the set of Equifax/McDash matched loans as our universe in our analysis. Owing to the restrictions above, this amounts to about 82% of the McDash universe. We also verify that we are correctly measuring the termination date and termination balance using the Equifax records by checking these variables against their McDash counterparts for the matched loans.

Over our period of interest (2008-9), our sample contains about 15 million mortgages per month; per MSA-month, we have on average 39,200 mortgages. One way to assess the coverage of our sample is to compare the outstanding mortgage balances by MSA to those in the FRBNY Consumer Credit Panel (CCP). The balances in our sample correspond on average to 29% of those in the CCP (with little variation over time), with a cross-sectional standard deviation across MSAs of 5% (the 25th percentile is at 26%, the 75th percentile at 32%). Since we start with a 50% random sample from CRISM and apply some filters as explained above, this means that CRISM covers over 60% of outstanding mortgages over this period.

### A.2.2 *Measuring Refinancing Propensities*

Our goal is to measure the proportion of outstanding loans in an MSA that were refinanced in a given month. For the denominator, we start with all outstanding first liens (where lien type is measured using the McDash variable) in our Equifax/McDash matched universe, but exclude in each month loans that terminate in the next month because they were transferred to another servicer or terminate

---

<sup>1</sup>This restriction allows us to infer the origination month, origination balance, and balance of the third largest loan of any loan type even though this information does not appear explicitly in Equifax, where if the third largest loan is also the newest loan, we assume its origination month to be the first month it appears in Equifax. We also drop loans that do not have complete consecutive Equifax records.

for unknown reasons (since we will be looking at the proportion of loans that are voluntarily paid off and refinanced).

We count a loan as being refinanced if: (1) its McDash termination type is a "voluntary payoff," and (2) for that consumer, there is another loan that is opened around the time of the first loan's termination on the same property (i.e. the new loan is a refinance, rather than a new purchase loan). More specifically, the most clear indicator that the new loan was a refinance is if the loan has a matching McDash loan (about 70%), and that McDash loan is marked as a refinance loan (in McDash's purpose type variable). On the other hand, the loan is clearly a new purchase loan if the purpose type is marked as such. However, about 25% of McDash loans have purpose type "Unknown" or "Other," and about 30% of the new loans are not matched in McDash (they only appear in Equifax, since McDash does not cover the entire market) and thus have no purpose type attached.

We thus use the following rules to identify refinances. We start by looking for any loan in the Equifax data set that has an open date within 4 months of the McDash loan's termination date. We find at least one such loan for about 81% of the voluntary terminations in 2008 and 2009. We classify these new loans as a refinance if either:

- The loan also appears in McDash and is tagged as a refinance in the purpose-type variable (61% of the McDash-matched loans).
- The loan also appears in McDash and is tagged as an "Unknown" or "Other" purpose type, and has the same property zip code as the original loan.
- The loan appears only in Equifax but the borrower's Equifax address does not change in the 6 months following the termination of the original loan.

This allows us to compute our measure of interest, the balance-weighted refinance propensity, as (balance outstanding in t-1 of loans that were refinanced in month t) / (balance outstanding in McDash in month t-1 that does not terminate for unknown reason in month t).

As a check, we calculate the refinance propensities separately for the three different cases above (McDash, known purpose; McDash, unknown purpose; Equifax), and find that these refinance propensities are very similar.

### *A.2.3 Measuring Cash-outs*

To measure cash-out refinancings, we need to both identify refinances and how the balance of the new loan compares to the outstanding balance of the loan(s) paid off in the process.

We begin with Equifax/McDash first liens (again using the McDash lien type variable), and keep only those loans that have a McDash purpose type of refinance or unknown/other. Our algorithm to identify whether our new loan is a refinance is similar to the algorithm above. This time, we look for a loan (or loans) in Equifax that terminate(s) around the time when the new loan is originated and check that this loan looks like it was refinanced. We use McDash refinances rather than outstanding loans as our point of reference for these statistics so that we can better represent all refinances, rather than introducing potential bias through only seeing refinances of McDash loans.

Specifically, we call any loan in the Equifax data set that terminates between -1 and 4 months from our new loan's close date a "linked" loan, including first mortgages as well as closed-end seconds and HELOCs, and we call the new loan a refinance if:

- The loan is a known refinance in McDash. (For 86% of these, we find a linked loan in either McDash or Equifax. For the remaining 14%, we would consider these refinances where there was no previous loan on the property.)
- The loan has an "Unknown" or "Other" purpose type in McDash and a linked loan in McDash that has a matching property zip code.

- The loan has an "Unknown" or "Other" purpose type in McDash and a linked loan that appears only in Equifax, but the consumer's Equifax address does not change in the 6 months after the new loan was opened.

If there is more than one linked loan that is a first mortgage in Equifax, we link only the loan that is closest in balance to the origination amount of the new mortgage. We also allow to be linked only those Equifax loans that exist in the Equifax data for at least three months to prevent the refinanced loan balance from being counted in the old balance of the loan.

For each of these cases, we can then calculate the cash-out amount as the difference between the origination amount on the refinance loan and the balance of the linked loan(s) at termination. In order to capture the correct origination amount on the refinance loan, we want to ensure that we are also including any "piggyback" second liens that are opened with the refinance loan that we find in McDash. Thus, we look for any loan in the Equifax record linked to our refinance loan that has an Equifax open date within three months of our refinance loan and an origination balance of less than 25% of our loan's origination balance if labeled a first mortgage and less than 125% of the refinance loan's origination balance if labeled a HELOC or CES, and add the balance of these piggyback seconds to the refi origination amount when calculating cash-out amounts.<sup>2</sup> To eliminate outliers, we also drop cash-out and "cash-in" amounts that are greater than \$1,000,000. These amount to dropping less than 0.05% of the refinance loans.

At the MSA level, this allows us to calculate the amount cashed out relative to the total outstanding balance in month  $t-1$ . To estimate total dollar amounts cashed out, we scale up the amount cashed out by the ratio of total housing debt outstanding in an MSA according to the FRBNY Consumer Credit Panel (CCP) relative to the total outstanding balance in our CRISM sample. (The CCP amounts are available as end-of-quarter snapshots, so we interpolate between them to get a monthly series.)

In Figure A-9, we compare the total estimated quarterly cash-out amounts to those estimated on prime conventional loans by Freddie Mac.<sup>3</sup> The figure shows that the two series co-move closely and also show similar levels. The higher level in CRISM is expected, since the Freddie Mac series does not include subprime/Alt-A as well as FHA and VA loans.

#### A.2.4 Measuring CLTVs/Equity

We start with all matched first-lien McDash loans. For a given month, we take the corresponding Equifax record and assign all outstanding second liens to the outstanding first liens in Equifax using the rule that each second lien is assigned to the largest first lien (in balance terms) that was opened on or before the second lien's opening date. We then add the assigned second lien balance(s) to the McDash balance of our original loan as our measure of secured debt on a property, which is the numerator of CLTV. For the denominator, the estimated updated property value, we start from the appraisal amount of the property at the time of the McDash loan origination and update it based on the local home price index from CoreLogic (using the zip-code-level index if available, and the MSA-level index if not).

Equity is simply defined as  $1 - CLTV$ . When taking medians within an MSA (our measure  $E_{j,t}^{med}$ ), we weight individual observations by their current outstanding first-lien loan balance (from McDash).

#### A.2.5 Household-level Analysis of Car Spending Around Refinancing

In Section IV.D.1, we study the response of car purchases to refinancing at the borrower level. To do so, we start out with a random 50% sample of borrowers in our CRISM sample who refinance at some point over the year 2009. (We only use 50% for computational reasons.) We obtain monthly information

<sup>2</sup>We impose these upper bounds because we want to avoid picking up other first lien mortgages (to purchase another property) the borrower might originate at the same time.

<sup>3</sup>To make the two comparable, we multiply our CRISM total by  $1/0.9175$ , where 0.9175 is the share of mortgage balances in CRISM that is in MSAs (as opposed to micropolitan statistical areas or rural areas) as of November 2008.

on these borrowers' car loans from their Equifax credit records (we sum two categories, "auto bank"—loans provided by banks, credit unions, savings and loan associations—and "auto finance"—loans provided by automobile dealers and automobile financing companies) starting 6 months before the refinancing date until 12 months after. We only retain borrowers for whom there is only one refinancing in the data over this period. This leaves us with 676,425 refinancers.

We mark a borrower as obtaining a new car loan in a month if the total balance of car loans outstanding increases by \$2,000 or more (following Agarwal et al., 2017b); results are similar if we use different cutoffs. For Figure VI, we distinguish between non-cashout-refinances and cash-out refinances, where a refinance is categorized as the latter if 0.98 times the balance of the refinance loan (including simultaneously opened junior liens, as described in Section A.2.3) is at least \$5,000 above the balance of the old loan(s) that are paid off. Subtracting the 2 percent of the new loan amount is done in order to account for the fact that some of the cashed out amount may be used to cover costs associated with the refinancing. This threshold is close to the binary indicator used by GSEs, and conclusions are not sensitive to altering the cutoff. According to this metric, 44 percent of refinances in our 2009 sample were cash-outs.

#### A.2.6 HMDA

For robustness, in Figure A-5 we use a different measure of refinancing activity based on data made available as part of the Home Mortgage Disclosure Act (HMDA), which requires mortgage lenders to report information on mortgage applications and originations. The HMDA data are generally perceived to be the most comprehensive and representative source of information on mortgage applications and originations, with market coverage estimated to be around 90%.<sup>4</sup> For each application, HMDA reports the geographic location of the property, the desired loan amount, the loan purpose (purchase or refinance), and whether the loan application led to an origination, was rejected by the lender, or was withdrawn by the borrower.<sup>5</sup> While the public-use HMDA data contain only calendar year indicators, the private-use version of the data set (available to users within the Federal Reserve System) also contains the exact application date and the exact action date. The action date is the date on which the loan is originated, the application is rejected, or the application is withdrawn. These exact dates make the data suitable for high frequency event studies (see, for example, Fuster and Willen, 2010). In all our analysis using HMDA data, we retain only applications that led to originations (action code = 1), and always use the application date (rather than the action date). We drop multifamily properties and mortgages with an origination amount >\$3 million (about 0.015% of loans).

While the HMDA data are ideal for measuring the flow volume of mortgage origination activity across locations, it has two prominent limitations. First, for refinance loans, the HMDA data do not include any information on the loan that is paid off. As a result, we cannot use the HMDA data to estimate the extent to which households are removing cash from their mortgage during the refinancing process—a limitation we overcome with the CRISM data we focus on in the main paper. Second, the HMDA data do not include any information on the loans after they are originated. Thus, HMDA is not informative about how many outstanding mortgages there are in an MSA. The stock of outstanding mortgages is necessary to measure a refinancing propensity.

To obtain an estimate of the number of outstanding mortgages in each MSA, we supplement HMDA with data from the 2008 American Community Survey (ACS), which reports the number of outstanding mortgages (but not their amount) and the number of households for fine geographic areas. Since the ACS samples only a fraction of the population, we scale up the number of households based on Census information on the overall number of households in the US in 2008. We use the same scaling factor for the number of mortgages in each location. By combining the ACS data with the HMDA data, we can compute the number of loan originations per number of outstanding mortgages

---

<sup>4</sup>See, for instance Dell'Ariccia, Igan, and Laeven (2012).

<sup>5</sup>There are actually three designated loan types within the HMDA data: origination, refinancing, and home improvement. We combine the home improvement loans with the refinancing ones in our work below.

for each location within the U.S. For the analysis of refinance propensities around the 2001 recession, shown in Figure VIII in the main text, we use the same procedure but based on the 2000 Census.

The measures of MSA-level refinancing propensities in late 2008/early 2009 are highly correlated between the HMDA data and the CRISM data, once we account for the lag in CRISM relative to HMDA. The population-weighted cross-sectional correlation between the HMDA refinance propensity in December 2008 and the CRISM refinance propensity in January (February) 2009 is 0.87 (0.88). Pooling the second half of 2008 and the first half of 2009, the correlation between HMDA and CRISM propensities is 0.84 for the one-month-forward and 0.78 for the two-month-forward CRISM propensities.

### A.2.7 Other Data

We now briefly describe some additional data used in our analysis. We measure unemployment rates for each MSA using data from the BLS's Local Area Unemployment Statistics. Our measure of labor income is based on the Individual Income Tax ZIP Code Data made available by the Internal Revenue Service. We first cumulate wage and salary incomes at the MSA level and then divide by the number of tax returns. We exclude tax returns from the top income category (>\$200,000) since those households can play a dominant role in driving average income changes; however, they are likely not the ones for which payment-to-income constraints (which we want to proxy for) are most relevant. Including those households, using adjusted gross income instead of wage and salary income, using the growth over 2007-2008 instead of 2008-2009, or using the income level instead of the growth rate does not change any of our conclusions in the regression tables below.

Our MSA-level demographic controls come from the ACS. We combine the 2007 and 2008 data to ensure the sample sizes are large enough to minimize measurement error. We measure each MSA's age composition, education composition, the percentage of homeowners, and the percentage of households with a mortgage. We restrict the ACS data to those individuals between the ages of 21 and 75 (inclusive) that were not living in group quarters (e.g., dorms, prisons, or medical facilities).

## A.3 MODEL PROOFS AND DESCRIPTION OF NUMERICAL SOLUTION

We provide here the proof of the homogeneity of the value function as well as a description of our computational procedure.

To show the homogeneity property, we proceed by guess and verify. The value functions for refinancing and not refinancing are

$$\begin{aligned}
V^{noref_i}(\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, r^m, r, F, 1) \tilde{p}^{\sigma-1} &= \max_{\{\hat{a}'\}} \frac{(\tilde{a}(1+r) + \tilde{y} - \gamma r_0^m \tilde{x} - \hat{a}')^{1-\sigma}}{1-\sigma} \tilde{p}^{\sigma-1} \\
&\quad + \beta \mathbb{E}[V(\hat{a}' \frac{\tilde{x}'}{\tilde{x}}, \tilde{y}', \tilde{x}', r_0^m, r^{m'}, r', F', 1) (\tilde{p}')^{\sigma-1} | \tilde{y}, \tilde{x}, r^m, r, F, 1] \\
V^{ref_i}(\tilde{a}, \tilde{y}, \tilde{x}, r^m, r, F, 1) \tilde{p}^{\sigma-1} &= \max_{\{\hat{a}'\}} \frac{(\tilde{a}(1+r) + \tilde{y} - \gamma r^m + \gamma(\tilde{x} - 1) - F - \hat{a}')^{1-\sigma}}{1-\sigma} \tilde{p}^{\sigma-1} \\
&\quad + \beta \mathbb{E}[V(\hat{a}' \frac{\tilde{x}'}{\tilde{x}}, \tilde{y}', \frac{\tilde{x}'}{\tilde{x}}, r^m, r^{m'}, r', F', 1) (\tilde{p}')^{\sigma-1} | \tilde{y}, \tilde{x}, r^m, r, F, 1]
\end{aligned}$$

Then we can eliminate  $\tilde{p}$  as a state variable to obtain the transformed value function,

$$\begin{aligned}
J(\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, r^m, r, F) &= \max\{J^{noref_i}(\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, r^m, r, F), J^{ref_i}(\tilde{a}, \tilde{y}, \tilde{x}, r^m, r, F)\} \\
J^{noref_i}(\tilde{a}, \tilde{y}, \tilde{x}, r_0^m, r^m, r, F) &= \max_{\{\hat{a}'\}} \frac{(\tilde{a}(1+r) + \tilde{y} - \gamma r_0^m \tilde{x} - \hat{a}')^{1-\sigma}}{1-\sigma}
\end{aligned}$$

$$\begin{aligned}
& + \beta e^{(1-\sigma)(\mu_q - \pi)} \mathbb{E} \left[ J(\hat{a}' \frac{\tilde{x}'}{\tilde{x}}, \tilde{y}', \tilde{x}', r_0^m, r^{m'}, r', F') | \tilde{y}, \tilde{x}, r^m, r, F \right] \\
J^{refi}(\tilde{a}, \tilde{y}, \tilde{x}, r^m, r, F) &= \max_{\{\hat{a}'\}} \frac{(\tilde{a}(1+r) + \tilde{y} - \gamma r^m + \gamma(\tilde{x} - 1) - F - \hat{a}')^{1-\sigma}}{1-\sigma} \\
& + \beta e^{(1-\sigma)(\mu_q - \pi)} \mathbb{E} \left[ J(\hat{a}' \frac{\tilde{x}'}{\tilde{x}}, \tilde{y}', \frac{\tilde{x}'}{\tilde{x}}, r^m, r^{m'}, r', F') | \tilde{y}, \tilde{x}, r^m, r, F \right]
\end{aligned}$$

In order to solve the transformed value function, we discretize  $\log \tilde{x}$  using 60 grid points evenly spaced with width  $\mu_q$  between 0.45 and -1.025, 64 grid points for  $\tilde{a}$  between 0 and 1, with more grid points near the lower asset values to account for the concavity of the value function, and 46 grid points for  $\tilde{y}$  evenly spaced in logs between -0.5 and 0.5. The stochastic shock can take on 3 values: -1SD, 0, and +1SD with probabilities computed using the Tauchen algorithm. Households assume that interest rates will remain constant in the future, and the model is solved with both  $r^m = 0.06$  and  $r^m = 0.05$ . The short-term interest rate  $r$  is permanently set to 0.03. The model is then solved using value function iteration. Finally, the model is simulated using 50,000 households and 9 regions. Households are initialized at median income and no assets in a middle income, middle house price region and 300 years of the model are discarded as an initial burn-in. Using a longer burn-in period or changing initial conditions prior to the burn-in period leaves results unchanged.

A number of alternative models are explored in Sections VII. and VIII. which involve changes to the baseline computational setup.

In the version of the model with ARMs, we assume that the households with ARMs' current payment moves one-for-one with the current mortgage rate when not refinancing. In particular, the  $J^{norefi}$  is identical except that  $r_0^m$  is always equal to  $r^m$ .

We calibrate the ARM share in bad regions to 30 percent, the ARM share in the middle regions to 20 percent and in the good regions to 10 percent. As described in the text, this is a conservative calibration for assessing the importance of ARMs since it overstates the actual variation in interest rate flexibility across space in 2008 as most ARMs do not have substantive rate resets during the QE episode.

We next explore a version of the model in which the housing bust in 2008 is preceded by a house price boom. Specifically, we assume that in the period before the Great Recession, there is an aggregate house price increase of 10% and a regional shock of  $\pm 7.5\%$  that is perfectly negatively correlated with the shock during the bust. This roughly captures house price movements in the last year of the housing boom. We do not recalibrate parameters in this exercise to match the effects of QE1, but they are similar to the baseline.

We then move to a model which partially endogenizes the cash-out decision when refinancing. In particular, we let households choose between two different options when refinancing: 1) Extracting all of their housing equity when refinancing, as in our baseline. 2) Extracting no equity and only resetting the rate. In this model, we now have three value functions:  $J^{norefi}$ ,  $J^{refi}$  and  $J^{refi \text{ rate only}}$ .  $J^{refi \text{ and cash-out}}$  is identical to  $J^{refi}$  in the original problem (except with a continuation value that maximizes over three rather than two value functions). When doing a pure rate-refi, the mortgage balance is unchanged but the household pays a fixed cost to change their fixed rate to the current mortgage rate in the economy. This means that  $J^{refi \text{ rate only}}$  is identical to  $J^{norefi}$  except that the rate adjusts to the current mortgage rate and the household must pay the refinancing cost. Note also that this value function is identical to that for the ARM model above, except that the household must pay the fixed cost to obtain the current rate instead of obtaining it for free:

$$J^{refi \text{ rate only}}(\tilde{a}, \tilde{y}, \tilde{x}, r^m, r, F) = \max_{\{\hat{a}'\}} \frac{(\tilde{a}(1+r) + \tilde{y} - \gamma r^m \tilde{x} - F - \hat{a}')^{1-\sigma}}{1-\sigma}$$

$$+ \beta e^{(1-\sigma)(\mu_q - \pi)} \mathbb{E} \left[ J(\hat{a}' \frac{\tilde{x}'}{\tilde{x}}, \tilde{y}', \tilde{x}', r^m, r^{m'}, r', F') | \tilde{y}, \tilde{x}, r^m, r, F \right]$$

Also note that this model introduces no new parameters, so the calibration strategy is identical to that in the baseline model. Ultimately, few households in the model choose to do rate only-refinancing with no cash-out even when they have this option, because the general equity accumulation and extraction problem still plays a primary role in decisions. A household who is contemplating a rate only refinance today still knows that in the future, they will eventually want to extract equity. Since the fixed cost of refinancing is the same whether they extract equity or not today, it makes sense to extract equity when refinancing to secure the low rate rather than doing a rate refi today and then paying the fixed cost again in the near future to extract equity.

Since we write the above value functions for general interest rate processes, the statement of the problem with stochastic interest rates is identical to that in the baseline model with a one-time unanticipated shock. Computationally, in the baseline model with a one-time shock, we only need to solve the model for two values of  $r^m$  to compute impulse responses, and we do not need to calculate expectations over  $r^m$ . In the model with stochastic mortgage rates,  $r^m$  takes on 5 values with probabilities computed using the Tauchen algorithm, and this state-variable enters expectations in the value function.

## A.4 APPENDIX TABLES AND FIGURES

This section provides additional tables and figures referred to in the main text.

- Table A-1 provides descriptive statistics on the 381 MSAs in our sample, including all the local control variables used in regressions reported in Tables I as well as Tables A-2 to A-5.
- Table A-2 documents the correlations between  $E_{Nov2008}^{med}$  and other local controls.
- Table A-3 provides the results from regressions of refinancing propensities on  $E_{Nov2008}^{med}$  and other local controls, all interacted with a post-QE indicator (equation (1)), but at the state level rather than the MSA level as in Table I.
- Table A-4 provides the results from regressions of cash-out shares on  $E_{Nov2008}^{med}$  interacted with post-QE indicator and other local controls (including refinancing propensities in the last column), discussed in Section IV.D.
- Table A-5 provides the results from regressions of log(auto sales) on  $E_{Nov2008}^{med}$  interacted with post-QE indicator, refinancing propensities and cash-out shares, discussed in Section IV.D (footnote 21).
- Figure A-1 shows that refinancing activity in HMDA data follows similar patterns to those shown in Figure I, and that there was no discernible increase in purchase mortgage activity around QE1.
- Figure A-2 shows that  $E_{Nov2008}^{med}$  is highly correlated with local shares of borrowers that have  $CLTV > 80$  or  $CLTV > 100$ , illustrating that the equity of the median borrower correlates strongly with other moments of the equity distribution, as discussed in Section IV.B.
- Figure A-3 shows distributions of MSA-median and individual-level equity in January 2007 and November 2008, as discussed in Section IV.B.
- Figure A-4 shows the relationships between  $E_{Nov2008}^{med}$  and local house price growth over Jan 2007-Nov 2008, and between  $E_{Nov2008}^{med}$  and changes in the local unemployment rate over Jan 2007-Nov 2008, as discussed in Section IV.B.
- Figure A-5 shows that the patterns shown in Figure III are very similar when using the HMDA data, where we can sum originated refinance mortgages by their application date. The figures show that activity jumped right after the QE1 announcement, and more so in high equity MSAs.
- Figure A-6 shows that there was essentially no variation in rates on new mortgages between high and low equity MSAs, as discussed in Section IV.B.
- Figure A-7 shows that there was no bunching in PTI ratios and no differences across high and low equity MSAs in the PTI distribution in 2009, while there is strong bunching and differences across MSA groups in CLTVs, as discussed in Section IV.B.
- Figure A-8 shows that non-housing debt increased in high equity MSAs relative to low equity MSAs following QE1, as discussed in Section IV.D.
- Figure A-9 shows that cash-out amounts in CRISM comove closely with those in Freddie Mac data, as discussed in Appendix A.2.3.
- Figure A-10 shows that the household-level distribution of equity in the 2008 calibration of our model is a good fit to the empirical distribution shown in Figure A-3, as discussed in Section VI.C.
- Figure A-11 shows how the refinancing threshold in our model changes with assets and earnings.

- Figure A-12 shows the separate contributions of borrowers and lenders to the aggregate consumption impulse response in the 2008 baseline model shown in Figure XI.
- Figure A-13 shows that shifts in the mean of the equity distribution have effects on monetary policy that depend on the variance of the distribution, as discussed in Section VI.E.2.
- Figure A-14 shows the consumption response in the model under different assumptions about the share of lenders that are in the domestic economy, as discussed in Section VIII.A.
- Figure A-15 shows the consumption response in a version of the model where income is partly endogenous to consumption, as discussed in Section VIII.A.
- Figure A-16 shows how ARM shares as of November 2008 and ARM payment reductions over Nov 2008-June 2009 are related to  $E_{Nov2008}^{med}$ , as discussed in Section VIII.B.1.
- Figures A-17-A-19 show results from additional robustness checks discussed in Section VIII.

**Table A-1: Descriptive Statistics.** Data on 381 MSAs; statistics are unweighted.

	Mean	SD	p10	p25	p50	p75	p90
Median equity share ( $E^{med}$ ), Jan 2007	0.293	0.066	0.209	0.243	0.289	0.345	0.383
Median equity share ( $E^{med}$ ), Nov 2008	0.160	0.110	0.015	0.120	0.190	0.230	0.261
$\Delta$ House Price Index, Jan 2007-Nov 2008	-0.111	0.113	-0.286	-0.161	-0.086	-0.033	0.010
$\Delta$ Unemployment, Jan 2007-Nov 2008	2.297	1.370	0.700	1.400	2.100	3.000	4.100
$\Delta$ Labor Income, 2008-2009	0.003	0.022	-0.022	-0.009	0.003	0.017	0.025
<i>Average mortgage characteristics as of Nov 2008 (based on CRISM):</i>							
FICO score	701.8	17.4	679.4	689.4	701.6	714.9	723.5
Current interest rate (%)	6.23	0.16	6.02	6.13	6.23	6.34	6.43
Loan age (months)	39.3	3.8	34.6	36.6	39.1	41.6	44.8
Share jumbos (based on current balance)	0.046	0.048	0.007	0.014	0.029	0.063	0.115
Average balance of non-jumbo loans (1000s)	130.7	46.2	87.3	100.0	117.3	153.2	181.2
Share adjustable-rate mortgages	0.136	0.098	0.057	0.070	0.098	0.171	0.272
Share GSE securitized	0.615	0.097	0.498	0.572	0.631	0.676	0.721
Share privately securitized	0.158	0.086	0.083	0.103	0.127	0.180	0.262
<i>Local demographics (based on ACS):</i>							
Years of education (shares)							
12	0.147	0.033	0.105	0.124	0.146	0.170	0.192
13-15	0.315	0.042	0.262	0.287	0.316	0.339	0.371
16	0.172	0.048	0.112	0.135	0.168	0.203	0.234
>16	0.266	0.026	0.236	0.250	0.263	0.281	0.300
Age group (shares)							
31-45	0.286	0.026	0.252	0.271	0.285	0.303	0.318
46-40	0.340	0.024	0.311	0.326	0.340	0.356	0.370
>60	0.206	0.038	0.167	0.183	0.202	0.223	0.244
Homeowners (share)	0.779	0.053	0.712	0.751	0.785	0.813	0.839
Mortgage borrowers (share)	0.543	0.065	0.454	0.505	0.552	0.591	0.619

Table shows descriptive statistics for all 381 MSAs in our analysis sample, including the distribution of median equity shares ( $E^{med}$ ) in January 2007 and November 2008, the distribution of house price and unemployment rate changes (in percent and percentage points, respectively) between January 2007 and November 2008, the distribution of changes in average labor income between 2008 and 2009, distributions of a number of characteristics of the outstanding mortgages in each MSA as of November 2008 (taking balance-weighted averages within each MSA), and local demographic characteristics as of 2008. For years of education and age groups, the base categories (<12 years of education; ages 21-30) are not shown. The share of mortgage borrowers is relative to all households, not just homeowners.

**Table A-2: Relationships between Median Equity and Unemployment Increases as well as Various Average Characteristics of Outstanding Mortgages**

	(1)	(2)	(3)	(4)	(5)	(6)
$\Delta$ Unemployment, Jan 2007-Nov 2008	-0.0597*** (0.00877)					-0.00236 (0.00434)
$\Delta$ Labor Income, 2008-09		3.705*** (0.513)				0.423 (0.257)
FICO score			0.00404*** (0.000661)			0.00528*** (0.000627)
Current interest rate (%)				-0.362*** (0.110)		0.347*** (0.0662)
Loan age (months)				0.00238 (0.00413)		-0.000393 (0.00142)
Share jumbos (based on current balance)				-0.473** (0.227)		0.661*** (0.125)
Average balance (non-jumbo)				-0.0189 (0.0467)		0.169*** (0.0280)
Share adjustable-rate mortgages					-1.128*** (0.321)	-0.942*** (0.150)
Share GSE securitized					0.0793 (0.124)	-0.437*** (0.0643)
Share privately securitized					0.956** (0.409)	-0.642*** (0.217)
Constant	0.302*** (0.0208)	0.159*** (0.0107)	-2.690*** (0.467)	2.365*** (0.766)	0.126 (0.0910)	-4.621*** (0.761)
Demographics	N	N	N	N	N	Y
N	381	381	381	381	381	381
Adj. $R^2$	0.36	0.31	0.30	0.16	0.17	0.85

Table shows the results of regressions of median equity as of November 2008 ( $E_{i,Nov2008}^{med}$ ) on various other variables observed as of November 2008 (and shown in Table A-1). Sample consists of 381 MSAs. MSAs are weighted by their 2008 population. Robust standard errors in parentheses. Significance: \*  $p < 0.1$ , \*\*  $p < 0.05$ , \*\*\*  $p < 0.01$ .

**Table A-3: Responses of Local Refinancing to Equity: State-Level Robustness**

	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
$E_{No2008}^{fixed} \times \text{postQE}$	1.788*** (0.551)	1.379** (0.573)	1.577** (0.726)	1.214** (0.525)	0.887*** (0.126)	2.099*** (0.483)	1.528*** (0.297)	0.895** (0.371)
$\Delta LUR_{Jan07-Not08} \times \text{postQE}$		-0.0602 (0.0451)						-0.0145 (0.0257)
$\Delta Income_{2008-09} \times \text{postQE}$			3.283 (4.314)					-2.675 (2.745)
FICO $\times$ postQE				0.0114*** (0.00241)				0.00371 (0.00390)
Current int. rate $\times$ postQE					-2.006*** (0.185)			-1.453*** (0.478)
Loan age $\times$ postQE					-0.0348*** (0.00705)			-0.0301** (0.0113)
Jumbo share $\times$ postQE					-2.630*** (0.595)			-2.656** (1.237)
Average balance (non-jumbo) $\times$ postQE					-0.294*** (0.0434)			-0.211 (0.164)
ARM share $\times$ postQE						3.051*** (0.870)		0.295 (0.833)
GSE share $\times$ postQE						1.244* (0.684)		0.504 (0.690)
Private sec. share $\times$ postQE						-2.640* (1.327)		-0.0753 (1.282)
Demographics $\times$ postQE	N	N	N	N	N	N	N	Y
State fixed effects	Y	Y	Y	Y	Y	Y	Y	Y
Month fixed effects	Y	Y	Y	Y	Y	Y	Y	Y
Adj. $R^2$	0.90	0.90	0.90	0.91	0.93	0.91	0.92	0.93
Adj. $R^2$ (within)	0.19	0.21	0.19	0.29	0.41	0.29	0.32	0.41
Observations	600	600	600	600	600	600	600	600

Table repeats the results from Table 1 but using state rather than MSA level refinancing and median equity. States are weighted by their 2008 population. Robust standard errors (clustered by state) in parentheses. Significance: \*  $p < 0.1$ , \*\*  $p < 0.05$ , \*\*\*  $p < 0.01$ .

**Table A-4: The Responsiveness of Cash-Out Refinancing Activity to Equity and Other Local Characteristics around QE1**

	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
$E_{Nov2008}^{ref} \times \text{postQE}$	0.167*** (0.0224)	0.138*** (0.0266)	0.147*** (0.0271)	0.103*** (0.0233)	0.123*** (0.0177)	0.171*** (0.0248)	0.157*** (0.0189)	0.0458** (0.0207)	0.0626*** (0.0137)
$\Delta UR_{Jan07-Nov08} \times \text{postQE}$		-0.00479*** (0.00176)						-0.00414*** (0.00145)	
$\Delta Income_{2008-09} \times \text{postQE}$			0.236** (0.117)					0.0303 (0.0906)	
FICO $\times$ postQE				0.000862*** (0.0000968)				0.000297 (0.000227)	
Current int. rate $\times$ postQE					-0.115*** (0.0146)			-0.112*** (0.0231)	
Loan age $\times$ postQE					-0.00140*** (0.000434)			-0.00219*** (0.000567)	
Jumbo share $\times$ postQE					-0.147*** (0.0398)			-0.0226 (0.0472)	
Average balance (non-jumbo) $\times$ postQE					-0.00633 (0.00537)			-0.00454 (0.0123)	
ARM share $\times$ postQE						0.00399 (0.0493)		-0.230*** (0.0435)	
GSE share $\times$ postQE						0.131*** (0.0291)		0.0437* (0.0251)	
Private sec. share $\times$ postQE						0.0990 (0.0663)		0.266*** (0.0667)	
Refinancing propensity									0.0610*** (0.00331)
Demographics $\times$ postQE	N	N	N	N	N	N	Y	Y	N
MSA fixed effects	Y	Y	Y	Y	Y	Y	Y	Y	Y
Month fixed effects	Y	Y	Y	Y	Y	Y	Y	Y	Y
Adj. $R^2$	0.80	0.80	0.80	0.81	0.81	0.80	0.80	0.82	0.84
Adj. $R^2$ (within)	0.12	0.12	0.12	0.15	0.17	0.13	0.14	0.20	0.32
Observations	4572	4572	4572	4572	4572	4572	4572	4572	4572

Table shows results from regressions of monthly equity removed (relative to outstanding balances) in 381 MSAs from August 2008 to July 2009, measured in CRISM, on median equity in each MSA interacted with a dummy "postQE" that equals one for the period February–July 2009, and other variables also interacted with postQE. Demographic controls in columns 7 and 8 are location-specific shares of individuals with different years of education: 12,13-15,16,>16 (<12 is omitted), shares of individuals with ages: 31-45,46-60,>61 (21-30 is omitted), homeowner shares and the share of households with mortgages, from the ACS. Each of these demographic controls is interacted with "postQE" to allow for differential responses to rate declines. All regressions also include MSA and month fixed effects. For reference, the average monthly equity removed over August 2008–January 2009 was 0.09 percent of outstanding balances, while over February–July 2009 it was 0.14 percent of outstanding balances. Descriptive statistics of explanatory variables are provided in Table A-1. MSAs are weighted by their 2008 population. Robust standard errors (clustered by MSA) in parentheses. Significance: \*  $p < 0.1$ , \*\*  $p < 0.05$ , \*\*\*  $p < 0.01$ .


Table A-5: The Responsiveness of New Vehicle Spending around QE1

	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
$E_{Nov2008}^{med} \times \text{postQE}$	0.389*** (0.0851)	0.246** (0.113)	0.227*** (0.0574)					0.104 (0.129)	-0.174 (0.144)
$E_{Nov2008}^{med} \times \text{time trend (monthly)}$		0.0103 (0.00918)	0.0110*** (0.00316)					0.0120 (0.00982)	0.0118 (0.00969)
(Refinancing propensity) <sub>t-2</sub>				0.0994*** (0.0244)	0.116*** (0.0206)			0.0874*** (0.0212)	0.0809*** (0.0227)
(Cashout/balance) <sub>t-2</sub>						0.485*** (0.165)	0.369*** (0.0923)	0.0511 (0.0621)	0.00689 (0.0513)
Other cont. $\times$ postQE	N	N	N	N	N	N	N	N	N
MSA fixed effects	Y	Y	Y	Y	Y	Y	Y	Y	Y
Month fixed effects	Y	Y	Y	Y	Y	Y	Y	Y	Y
Adj. R <sup>2</sup>	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Adj. R <sup>2</sup> (within)	0.04	0.03	0.05	0.04	0.04	0.01	0.01	0.05	0.09
Observations	4572	9144	18288	4572	9144	4572	9144	9144	9144
Date range	200808.200907	200801.200912	200701.201012	200808.200907	200801.200912	200808.200907	200801.200912	200801.200912	200801.200912

Column 1 shows results from regression of monthly log(auto sales) in 381 MSAs on median equity ( $E^{med}$ ) in each MSA (as of November 2008) interacted with a dummy "postQE" that equals one from February 2009 onward. In columns 2 and 3, the sample period is extended and a monthly trend interacted with  $E_{Nov2008}^{med}$  is added. In columns 4 and 5, log(auto sales) is directly regressed on two-months-lagged local refinancing propensities; in columns 6 and 7 the same is repeated for local cash-out amounts (relative to outstanding balance). Columns 8 and 9 add  $E_{Nov2008}^{med} \times \text{postQE}$  and both refinancing measures simultaneously; in column 9 we further add all mortgage market and demographic controls interacted with postQE (as in the last column of Table 1). All regressions also include MSA and month fixed effects. MSAs are weighted by their 2008 population. Robust standard errors (clustered by MSA) in parentheses. Auto sales are from R.L. Polk; refinancing propensities and cash-out fractions are measured in CRISM. Significance: \*  $p < 0.1$ , \*\*  $p < 0.05$ , \*\*\*  $p < 0.01$ .

**Figure A-1: Mortgage Activity in the US over 2000-2012, Based on HMDA Data**

**(a): Refinance Mortgage Originations**



**(b): Purchase Mortgage Originations**




Figure shows mortgage originations on 1-4 unit homes in HMDA, by month in which the borrower applied for the loan. The vertical line indicates the month of the QE1 announcement (November 2008).

**Figure A-2: Median Equity vs. Fraction of Borrowers over CLTV 80 or CLTV 100 Thresholds, as of November 2008.**





Figure shows the relationship between median equity in an MSA as of November 2008 ( $E_{j,Nov2008}^{med}$ ) and the share of borrowers in the MSA who have an estimated CLTV in the same month higher than 80 percent (black circles) or higher than 100 percent (gray circles). Equity/CLTVs are measured based on CRISM. Each observation is an MSA, with 381 in total (per series). The size of the circle represents the 2008 population of the MSA.

**Figure A-3: Distributions of Borrowers' Equity in their Homes — MSA Medians and Individual Level**





Panel (a) shows kernel density of  $E_{j,t}^{med}$  across 381 MSAs in January 2007 and November 2008; MSAs are weighted by their 2008 population. Panel (b) shows kernel density of individual borrower equity in January 2007 and November 2008; borrowers are weighted by loan amount. Individual equity is more disperse than median equity at the MSA level because individual variation has life-cycle and other idiosyncratic components that are large relative to cross-region variation.

**Figure A-4: Relationship between Equity and Other Measures of Economic Activity.**

**(a): House Price Growth vs. Median Equity**


**(b): Unemployment Rate Change vs. Median Equity**




Panel (a) shows MSA house price growth between January 2007 and November 2008 vs. the median borrower's equity (as a share of estimated home value) in the MSA in November 2008. Each observation is an MSA, with 381 in total. The size of the circle represents the 2008 population of the MSA. The figure also shows the simple (population weighted) regression through the scatter plot: a 1 percent decline in house prices is associated with a 0.83 percentage point decrease in median equity (standard error 0.07) with an R-squared of 0.69. Panel (b) shows the change in an MSA's unemployment rate between January 2007 and November 2008 vs. the median borrower's equity (as a share of estimated home value) in the MSA in November 2008. The simple regression line shows that a 1 percentage point increase in the unemployment rate is associated with a 6.0 percentage point decline in median equity (standard error 0.09) with an R-squared of 0.36.

**Figure A-5: Mortgage Refinance Activity 2008-2009 in Top and Bottom Quartile of MSAs Defined by Median Equity in November 2008, Based on HMDA Data**


**(a): Refinance Origination Volumes**



**(b): Refinance Propensities**



**(c): Total Origination Volumes (Refinance and Purchase)**




Panel (a) shows total mortgage refinance volume in HMDA by month in which borrower applied for the mortgage, where months are re-defined such that they start on the 25th day of the prior month. Panel (b) shows corresponding refinance propensities, defined as the number of refinance originations in HMDA divided by the total number of mortgages outstanding as measured in the 2008 American Community Survey. Panel (c) shows total mortgage origination volume (purchase and refinance) in HMDA by month in which borrower applied for the mortgage. In all three panels, calculations are done at the level of MSA quartile groups and vertical lines indicate the month of the QE1 announcement (November 2008).

**Figure A-6: No Spatial Variation in Mortgage Interest Rates**

**(a): Raw Interest Rates by Equity Quartile**

**(b): Interest Rate Gaps After Controlling for Observables**



Panel (a) shows average interest rate on newly originated non-purchase mortgages in CRISM in the top and bottom MSA quartiles by  $E_{j,Nov2008}^{med}$ , showing that the evolution of mortgage rates was almost identical across locations. In panel (b), the black line shows the difference in the average interest rate on newly originated mortgages relative to its level in November 2008. The gray line shows the gap between average rate residuals in the top and bottom MSA quartiles by  $E_{j,Nov2008}^{med}$ . Rate residuals are obtained following [Hurst et al. \(2016\)](#), by regressing each newly originated mortgage's interest rate on quadratic functions of FICO and LTV, and dummies for different loan purposes (purchase, rate refi, cashout refi, unknown), all interacted with month dummies. The gap averages only around 5 basis points over our sample and does not increase after QE1.

**Figure A-7: 2009 Distributions of PTI and CLTV for Top and Bottom Quartile of MSAs Defined by Median Borrower Equity in November 2008**




Figure shows the distribution of PTI and CLTV at origination in high and low equity MSA groups for loans originated in 2009 using the pooled sample of loans acquired by Fannie Mae and Freddie Mac in Single Family Loan Performance (SFLP) Data. In total, we observe 1,886,365 originations in the highest equity quartile and 1,514,085 originations in the lowest equity quartile. We set the 48,537 loans with missing PTI equal to 0.65 since SFLP does not report PTI above 0.65, but results are similar when instead excluding these loans. Panel (a) shows that the distribution of PTI exhibits little bunching and is similar in both high and low equity MSAs (as listed in Appendix A.1). Panel (b) shows that the distribution of CLTV (for the flow of new mortgages in SFLP) exhibits substantial bunching and that CLTVs on newly originated loans tend to be higher in MSAs where borrowers have less equity in outstanding mortgages (as measured in CRISM).

**Figure A-8: Evolution of Non-Housing Debt for Top and Bottom Quartile of MSAs Defined by Median Borrower Equity in November 2008**




Figure shows level (panel (a)) and quarterly change (panel (b)) of non-housing debt per person in the FRBNY Consumer Credit Panel in the top and bottom MSA quartiles by  $E_{j,Nov2008}^{med}$ . Non-housing debt includes auto loans, credit card balances, student loans, consumer finance loans (sales financing, personal loans), retail loans (department stores, home furnishings, gas, etc.), and unspecified "other" loans.

**Figure A-9: Estimated Cash-out Amounts from Freddie Mac vs. in our CRISM data**





Figure shows estimated quarterly cash-out volumes on prime conventional (non-government) mortgages estimated by Freddie Mac (obtained from [http://www.freddiemac.com/finance/docs/q4\\_refinance\\_2014.xls](http://www.freddiemac.com/finance/docs/q4_refinance_2014.xls)), as well as those we obtain based on the CRISM data (which also include FHA/VA loans) after scaling up as explained in Section A.2.3.

**Figure A-10: 2008 Household Equity Distribution: Model vs. Data**



This figure compares the household level density of equity in 2008 with no reduction in interest rates to the empirical distribution just prior to QE1 in November 2008.

**Figure A-11: Relationship between Refinancing Threshold, Equity and Income**




Figure shows refinancing threshold for each asset and income value for low fixed cost.

**Figure A-12: Borrower and Lender Contribution to Aggregate Consumption Impulse**




Figure shows the separate contributions of borrowers and lenders to the aggregate consumption impulse response in the 2008 baseline model shown in Figure XI.

**Figure A-13: Effect of  $\sigma$  on  $\Delta IRF_{f_0(\mu,\sigma)}$**






Figure shows how much a 10% increase in equity changes the aggregate consumption response to a 1% decrease in  $r^m$ , for different values of the cross-region standard deviation of equity. Let  $IRF_{f_0(\mu,\sigma)} = \frac{\Delta C}{\Delta r^m}$  be the response on impact (in the first year) of consumption to a 1% decline in interest rates given an initial equity distribution  $f_0$  with mean  $\mu$  and standard deviation  $\sigma$ . Then let  $\Delta IRF_{f_0(\mu,\sigma)} = \frac{IRF_{f_0(\mu+10\sigma)} - IRF_{f_0(\mu,\sigma)}}{IRF_{f_0(\mu,\sigma)}}$ .  $\Delta IRF_{f_0(\mu,\sigma)}$  measures how a 10 percentage point increase in the mean of the equity distribution affects the impulse response of consumption to interest rates. This figure plots  $\Delta IRF_{f_0(\mu,\sigma)}$  as we change the cross-region standard deviation of equity  $\sigma$ . The leftmost point in the figure sets  $f_0(\mu,\sigma)$  equal to the stochastic steady-state distribution, and then we steadily increase the cross-region standard deviation of equity. In the stochastic steady-state with  $\sigma = 2.5\%$ , a 10% increase in house prices increases the aggregate consumption response to a 1% rate decline by almost 60%. However, when  $\sigma$  is higher, this same mean increase in house prices has a smaller effect on the response of consumption to a rate drop.

**Figure A-14: Importance of GE Effects from Lenders' Consumption**



This figure shows aggregate consumption IRFs for alternative assumptions on what share of mortgage debt is held by domestic households, whose income will fall when interest rates decline.

**Figure A-15: Endogenous Income Effects**



This figure shows outcomes for a version of the model which partially endogenizes income.

**Figure A-16: Adjustable-Rate Mortgage Shares pre-QE1 and Payment Reductions over Nov 2008 – June 2009**

**(a): ARM Shares vs. Median Equity**

**(b): Sizeable ARM Payment Reductions vs. Median Equity**







Figure shows scatter plots of the balance-weighted fraction of adjustable-rate mortgages (ARMs) in a given MSA (panel a) or the balance-weighted fraction that are ARMs and experience a rate reduction of 1 percentage point or more over November 2008 – June 2009 (panel b), as measured in the CRISM data, versus the median equity share ( $E^{med}$ ) within the MSA as of November 2008. When computing the share with rate drops, we also require that the recorded required monthly payment not increase over the same period (which may indicate that the loan's IO period expired). The size of the circle represents the 2008 population of the MSA. The gray lines represent simple regression lines fitting the scatter plot (population weighted). The regression line in panel (b) has a slope of -0.059 (s.e. = 0.009). Meanwhile, regressing the 6-month refinancing propensity (from January-June 2009) on  $E_{j,Nov2008}^{med}$  yields a coefficient of +0.147 (s.e. = 0.028).

**Figure A-17: Accounting for Ex-Ante Heterogeneity**


**(a): Match ARM-Share**




**(b): Spending responses of ARM vs. FRM borrowers**



**(c): Reduce Equity-Refi Elasticity**




**(d): Boom-Bust**



Panel (a) repeats Figure XI in a model with both FRM and ARMs calibrated to match the regional differences with house prices in the data. Panel (b) shows the average spending response of ARM borrowers, FRM borrowers and their share-weighted averages in 2008 compared to 2001. Note that the share-weighted average borrower average is not identical to the aggregate spending response since it includes no lender responses. Panel (c) repeats Figure XI in a model where fixed costs are doubled. This roughly halves the relationship between regional equity and refinancing. Panel (d) repeats Figure XI in a model where regions with the largest house price declines experience a prior house price boom.


Figure A-18: Robustness Results




This figure repeats Figure XI in several alternative models. In panel (a) households can choose between full cash-out and no cash-out refinancing. In panel (b) interest rate movements are stochastic instead of a one-time shock. In panel (c)  $r$  and  $r^m$  both decline, with a constant spread. In panel (d), only  $r$  declines.

Figure A-19: More Robustness Results


(a): Include temporary income shocks



(b): Correlated income and hp shocks



(c): Double House Price Growth



This figure repeats Figure XI in several alternative models. In panel (a) households experience i.i.d. transitory income shocks. In panel (b), regional house price and income shocks are perfectly correlated instead of uncorrelated. In panel (c) trend house price growth is doubled.